

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, GENERAL NOTES, & STATE STANDARDS
3-4	SUMMARY OF QUANTITIES
5	SCHEDULE OF LANDSCAPE ITEMS
6	TREE DETAILS
7	WORK ORDER
8-9	CDOT - TREE PLANTING LOCATIONS
10	UIC - TREE PLANTING LOCATIONS
11-12	CDOT - TREE WATERING & TREE CARE LOCATIONS
13-14	UIC - TREE WATERING & TREE CARE LOCATIONS
15-16	DISTRICT DETAILS

HIGHWAY STANDARDS

- 701501-06 URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
- 701601-09 URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NON TRAVERSABLE MEDIAN
- 701701-09 URBAN LANE CLOSURE, MULTILANE INTERSECTION
- 701801-05 SIDEWALK, CORNER OR CROSSWALK CLOSURE
- 701901-03 TRAFFIC CONTROL DEVICES

701006-05
701101-04
701427-02

GENERAL NOTES

PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR MUST SUBMIT A PROPOSED CONSTRUCTION SCHEDULE IN A FORMAT APPROVED BY THE ENGINEER. NO WORK WILL BE PERMITTED TO PROCEED UNTIL THE PROPOSED SCHEDULE IS REVIEWED AND APPROVED BY THE ENGINEER.

IN AREAS WHERE MULTIPLE LOCATIONS ARE PROPOSED TO BE CONSTRUCTED, THE CONTRACTOR WILL BE REQUIRED TO STAGE WORK SO AS NOT TO ADVERSELY AFFECT THE FLOW OF PEDESTRIAN VEHICULAR TRAFFIC WITHIN THE GENERAL AREA. THE PROPOSED CONSTRUCTION SCHEDULE SHOULD REFLECT A PROGRESSION OF WORK THAT WILL MAINTAIN TRAFFIC TO THE SATISFACTION OF THE ENGINEER.

THE CITY RESERVES THE RIGHT TO ORDER, IN WRITING, CHANGES IN THE WORK OR THE CONTRACT TIME. THESE CHANGES MAY CONSIST OF ADDITIONS, DELETIONS OR OTHER REVISIONS, AT THE DISCRETION OF THE CITY.

WHEN UNFORESEEN CIRCUMSTANCES IMPACT THE CONTRACTOR'S APPROVED CONSTRUCTION SCHEDULE, IT MAY BE NECESSARY TO ADJUST OR REVISE THE SCHEDULE IN ORDER TO MAINTAIN PROGRESS AND PROVIDE FOR PEDESTRIAN AND VEHICULAR SAFETY. THE CONTRACTOR WILL COOPERATE FULLY WITH THE CITY IN THIS REGARD.

LANE CLOSURES, WORK ZONE RESTRICTIONS, REVISED WORK DAY HOURS AND WEEKEND OR HOLIDAY WORK SCHEDULES ARE SUBJECT TO THE APPROVAL OF THE COMMISSIONER. THE CONTRACTOR MUST RECEIVE WRITTEN AUTHORIZATION, EITHER BY PERMIT OR NOTIFICATION BY THE ENGINEER, BEFORE PROCEEDING WITH WORK UNDER THESE CIRCUMSTANCES.

BEFORE STARTING ANY EXCAVATION ON CDOT R.O.W., THE CONTRACTOR SHALL CALL C.U.A.N. (CHICAGO UTILITY ALERT NETWORK) AT 312-744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRICAL, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED).

BEFORE STARTING ANY EXCAVATION ON THE UIC R.O.W., THE CONTRACTOR SHALL CALL 312-996-2883 FOR FIELD LOCATIONS OF BURIED ELECTRICAL FACILITIES, 312-996-2816 FOR FIELD LOCATIONS OF BURIED IRRIGATION, AND 312-996-0746 FOR FIELD LOCATIONS OF BURIED FIBER OPTIC FACILITIES. THE CONTRACTOR SHALL CALL 312-413-5800 BEFORE STARTING ANY WORK ON UIC PARKING LOTS. SEVEN (7) DAY NOTIFICATION IS REQUIRED.

THE CONTRACTOR SHALL COORDINATE ACTIVITIES WITH UTILITY COMPANIES, THE CITY OF CHICAGO, AND THE UIC CAMPUS.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM I.D.O.T. OR THE CITY OF CHICAGO.

PAY ITEMS IN THE SUMMARY OF QUANTITIES HAVE BEEN ESTIMATED, IF, IN THE ENGINEER'S OPINION, THE WORK IS NOT REQUIRED, THE ITEM WILL BE DEDUCTED FROM THE CONTRACT AND NO ADDITIONAL COMPENSATION TO THE CONTRACTOR WILL BE ALLOWED.

ANY WORK WITHIN A LANDSCAPED MEDIAN REQUIRES A LANE CLOSURE AND USE OF AN ARROW BOARD PER IDOT SPECIFICATIONS.

CONTRACTOR MUST ACQUIRE PERMITS FROM CHICAGO DEPARTMENT OF TRANSPORTATION (CDOT), CHICAGO BUREAU OF FORESTRY (BOF), AND CHICAGO DEPARTMENT OF WATER MANAGEMENT. THE PERMITS ARE DETAILED IN CDOT BOOK 3, PAGE DS-16, SUBMITTALS ITEM 7.

THE CONTRACTOR SHALL COORDINATE ALL ACTIVITIES WITH IDOT CONTRACT 60X37 (LANDSCAPE).

THE CONTRACTOR SHALL ORDER PLANT MATERIAL AND SUBMIT COMPLETED PLANT INSPECTION SHEETS TO IDOT BY JANUARY 31, 2015 TO ASSURE PLANT AVAILABILITY FOR THE SPRING PLANTING SEASON.

CONTRACTOR SHALL PERFORM DUE DILIGENCE IN LOCATING SPECIFIED PLANT MATERIAL.

NO SUBSTITUTIONS OF PLANT MATERIAL, QUANTITIES OR SIZES SHALL BE ALLOWED UNLESS APPROVED BY THE ENGINEER.

EXCAVATION BY AUGER OR OTHER MECHANICAL MEANS IS NOT ACCEPTABLE. HAND DIGGING OF ALL PLANT HOLES IS REQUIRED.

THE CONTRACTOR SHALL USE CARE IN GRADING OR EXCAVATING NEAR ANY AND ALL EXISTING ITEMS THAT WILL NOT BE REMOVED. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S OWN EXPENSE TO THE SATISFACTION OF THE ENGINEER.

WHENEVER, DURING CONSTRUCTION OPERATIONS, ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF DRAINAGE STRUCTURES SUCH THAT THE NATURAL FLOW OF WATER IS OBSTRUCTED, IT SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL UTILITY STRUCTURES SHALL BE FREE FROM DIRT AND DEBRIS. THE WORK SPECIFIED ABOVE WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST FOR CATCH BASINS AND MANHOLES TO BE ADJUSTED IN THIS CONTRACT.

ANY EXISTING STORM SEWER DAMAGED BY THE CONTRACTOR DURING CONSTRUCTION SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE CITY.

WATERING METHOD WILL BE APPROVED BY THE ENGINEER PRIOR TO WATERING.

COMMITMENT

NO WORK SHALL BE DONE PAST FRIDAY, MAY 8TH BY THE UIC FORUM AND THE UIC PAVILLION DUE TO SPECIAL SCHOOL EVENTS. ALL INSTALLATION AND RESTORATION WORK WITHIN THESE AREAS SHALL BE COMPLETED BY FRIDAY, MAY 8TH.

FILE NAME *	USER NAME * delrosarions	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES, & STATE STANDARDS	PLOT SCALE * 1/8"=1'-0"	CHECKED - _____	REVISED - _____	F.A.I. RTE. 90/94/290	SECTION 2014-050LS	COUNTY COOK	TOTAL SHEETS 16	SHEET NO. 2	
Default	0107014-shs-Landscape.dgn	DRAWN - _____	REVISED - _____			SCALE: _____	SHEET _____ OF _____ SHEETS	STA. _____ TO STA. _____	CONTRACT NO. 60Y66					
	PLOT DATE * 01/14/2014	DATE - _____	REVISED - _____			ILLINOIS FED. AID PROJECT								
						Rev.								