

SUMMARY OF QUANTITIES		LOCATION OF WORK		SHERIDAN ROAD AT GRAND AVENUE	SHERIDAN ROAD AT GLEN FLORA AVENUE	IL 137 (SHERIDAN RD) AT GREENWOOD AVENUE	IL 137 (SHERIDAN RD) AT MIRAFLORES AVENUE	IL 137 (SHERIDAN RD) AT YORK HOUSE ROAD	IL 137 (SHERIDAN RD) AT BEACH ROAD	IL 137 (SHERIDAN RD) AT WADSWORTH ROAD	IL 137 (SHERIDAN RD) AT 34TH STREET	IL 137 (SHERIDAN RD) AT 33RD STREET	IL 137 (SHERIDAN RD) AT 31ST STREET	IL 137 (SHERIDAN RD) AT 29TH STREET	IL 137 (SHERIDAN RD) AT 27TH STREET	IL 137 (SHERIDAN RD) AT 25TH STREET (SHILOH BLVD)	IL 137 (SHERIDAN RD) AT 23RD STREET	IL 137 (SHERIDAN RD) AT IL 173 (21ST ST)	INTERCONNECT-IL 137 (SHERIDAN RD) FROM GRAND AV TO WADSWORTH ROAD
				CONSTRUCTION CODES															
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0021 TRAFFIC SIGNALS															
* 20200100	EARTH EXCAVATION	CU YD	9	9															
* 42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	18	18															
* 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	890	890															
* 42400800	DETECTABLE WARNINGS	SO FT	88	88															
* 44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	18	18															
* 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	125	125															
* 44000600	SIDEWALK REMOVAL	SO FT	830	830															
* 60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	10	10															
* 60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	115	115															
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	30																
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1																
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	3																
67100100	MOBILIZATION	L SUM	1																
72000100	SIGN PANEL - TYPE 1	SO FT	40.50				19.50	21.00											

* SPECIALTY ITEM
 Δ = 11/6/2014 (Revised)