


ACE ACBRF A

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | URBAN | |
|----------|-----------------------------------|-------|----------------|---|---|
| | | | | CONST. CODE 80% FED 20% STATE ROADWAY 0004 RURAL | CONST. CODE 80% FED 20% STATE BRIDGE 0011 S. N. 098-0015 |
| 20200100 | EARTH EXCAVATION | CU YD | 1,580 | 1,580 | |
| 20400800 | FURNISHED EXCAVATION | CU YD | 630 | 630 | |
| 20700220 | POROUS GRANULAR EMBANKMENT | CU YD | 448 | | 448 |
| 20900110 | POROUS GRANULAR BACKFILL | CU YD | 250 | 250 | |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 4,820 | 4,820 | |
| 25000210 | SEEDING, CLASS 2A | ACRE | 1.25 | 1.25 | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 96 | 96 | |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 96 | 96 | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 96 | 96 | |
| 25100115 | MULCH, METHOD 2 | ACRE | 1.25 | 1.25 | |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 5,109 | 5,109 | |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 3,500 | 3,500 | |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 1,696 | 1,696 | |
| 28000500 | INLET AND PIPE PROTECTION | EACH | 4 | 4 | |

+ SPECIALTY ITEM

FILE NAME : H:\jpl\2014-05\9416346-025\MicroStation\026-C17-141-5001.dgn



1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME : brianf
DESIGNED - VLF
DRAWN - DJW
CHECKED - MAG
DATE - 8-14-14

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SCALE: N/A SHEET 1 OF 9 SHEETS STA. TO STA.

F.A.P. RTE. 646 SECTION 101 BR-3 COUNTY WHITESIDE TOTAL SHEETS 130 SHEET NO. 5 CONTRACT NO. 64C17
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT

Rev. 11-6-14