CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ACF CONST. CODE 80% FED 20% STATE ROADWAY 0004 RURAL	ACBRF CONST. CODE 80% FED 20% STATE BRIDGE 0011 S.N. 098-0015
			URBAN		
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	783	783	
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	7,210	7,210	
X5121800	PERMANENT STEEL SHEET PILING	SQ FT	12,893		12,893
X5860110	GRANULAR BACKFILL FOR STRUCTURES	CU YD	545		545
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
+ X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1	1	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	80		80
Z0004552	APPROACH SLAB REMOVAL	SQ YD	834	834	
Z0004638	PAVEMENT BREAKING	SQ YD	1,777	1,777	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	50		50
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	2,472		2,472
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	304		304
Z0062456	TEMPORARY PAVEMENT	SQ YD	1,430	1,430	

Rev. 11-6-14

FILE NAME = s:_pl\6280-6399\6346\025\Microsta\0264C17-sht-S001.dgn

STRAND ASSOCIATES 1170 SOUTH HOUBOLT ROAD JOLIET, ILLINOIS 60431 (815) 744-4200

USER NAME = brianf | PLOT SCALE = 20.0000 ' / in. | PLOT DATE = 8/14/2014

DESIGNED - VLF | DRAWN - DJW | CHECKED - MAG | DATE - 8-14-14

REVISED - | REVISED - | REVISED - | REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A | SHEET 8 OF 9 SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
646	101 BR-3	WHITESIDE	130	12
		CONTRACT NO. 64C17		

FED. ROAD DIST. NO. 2 | ILLINOIS | FED. AID PROJECT