


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN	
				CONST. CODE	CONST. CODE
				80% FED 20% STATE	80% FED 20% STATE
				ROADWAY	BRIDGE
				0004	0011
				RURAL	S. N. 098-0015
44004250	PAVED SHOULDER REMOVAL	SO YD	1,873	1,873	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	325	325	
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SO YD	1,721	1,721	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD	82.0		82.0
50200100	STRUCTURE EXCAVATION	CU YD	1,313		1,313
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	448		448
50300225	CONCRETE STRUCTURES	CU YD	778.0		778.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	643.0		643.0
50300260	BRIDGE DECK GROOVING	SO YD	1,307		1,307
50300300	PROTECTIVE COAT	SO YD	1,431		1,431
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	6,480		6,480
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	271,220		271,220

14

+ SPECIALTY ITEM

FILE NAME: s:\j\16300-639\5346\025\micr\con\5\m\025617-14-14\500.dwg



USER NAME: brianf
 PLOT SCALE: 20.0000' / 1" / 1"
 PLOT DATE: 8/14/2014

DESIGNED: VLF
 DRAWN: DJW
 CHECKED: MAG
 DATE: 8-14-14

REVISED: -
 REVISED: -
 REVISED: -
 REVISED: -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET 3 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
646	101 BR-3	WHITESIDE	130	7
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT			CONTRACT NO. 64C17	