


FILE NAME: I:\proj\62800-639\6346\025\mic\oa\5\1\028417.plt 9/20/14

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN	
				CONST. CODE	CONST. CODE
				80% FED 20% STATE	80% FED 20% STATE
				ROADWAY	BRIDGE
				0004	0011
				RURAL	S. N. 098-0015
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	783	783	
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SO FT	7,210	7,210	
X5121800	PERMANENT STEEL SHEET PILING	SO FT	12,893		12,893
X5860110	GRANULAR BACKFILL FOR STRUCTURES	CU YD	545		545
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
+ X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1	1	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	80		80
Z0004552	APPROACH SLAB REMOVAL	SO YD	834	834	
Z0004638	PAVEMENT BREAKING	SO YD	1,777	1,777	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	50		50
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SO FT	2,472		2,472
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	304		304
Z0062456	TEMPORARY PAVEMENT	SO YD	1,430	1,430	

19



USER NAME	• brianf	DESIGNED	- VLF	REVISED	-
DRAWN	- DJW	CHECKED	- MAG	REVISED	-
DATE	- 8-14-14			REVISED	-

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	N/A	SHEET 8	OF 9 SHEETS
STA.		TO STA.	

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
646	101 BR-3	WHITESIDE	130	12
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT			CONTRACT NO. 64C17	