


SUMMARY OF QUANTITIES					
				FUNDING: 80% FED : 20% STATE	
CONSTRUCTION CODE TYPE:			TOTAL	0004	0011
CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY	SN 008-0014 (EX) SN 008-0051 (PR)
52100520	ANCHOR BOLTS, 1"	EACH	24		24
54200229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	163	163	
54261624	CONCRETE END SECTION, STANDARD 542001, 24", 1:6	EACH	4	4	
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	72		72
60100080	FRENCH DRAINS	CU YD	6.0	6.0	
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	200.0	200.0	
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	
*63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	1142	1142	
63500105	DELINEATORS	EACH	4	4	
66500105	WOVEN WIRE FENCE, 4'	FOOT	1019	1019	
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	9	9	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	

SPECIALTY ITEMS

FILE NAME *	USER NAME * USER*	DESIGNED - RAC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	 Zroka Engineering, P.C. 4216 North Homewood Chicago, IL 60643	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILEL		DRAWN - SAW	REVISED -				646	5 BR-3	CARROLL	84	8
PLOT SCALE * SCALE*		CHECKED - DAZ	REVISED -				CONTRACT NO. 64084			ILLINOIS FED. AID PROJECT	
PLOT DATE * DATE*		DATE - 10-11-13	REVISED -	SCALE:	SHEET 4 OF 6 SHEETS	STA. TO STA.					