

SCHEDULE OF QUANTITIES

70301000	WORK ZONE PAVEMENT MARKING REMOVAL			
	SQ YD	LOCATION	DIR	REMARKS
	3497	600+82 TO 1020+30	EB	WHITE SKIP DASH
	1120	600+82 TO 1020+30	EB	YELLOW DIAGONAL LINES
	3497	1020+30 TO 600+82	WB	WHITE SKIP DASH
	1120	1020+30 TO 600+82	WB	YELLOW DIAGONAL LINES
TOTAL	9,234			
78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"			
	FOOT	LOCATION	DIR	REMARKS
	YELLOW			
	41948	600+82 TO 1020+30	EB	YELLOW EDGE LINE
	41948	1020+30 TO 600+82	WB	YELLOW EDGE LINE
SUBTOTAL	83896			
	WHITE			
	41948	600+82 TO 1020+30	EB	WHITE EDGE LINE
	41948	1020+30 TO 600+82	WB	WHITE EDGE LINE
SUBTOTAL	83896			
TOTAL	167,792			
78008330	POLYUREA PAVEMENT MARKING TYPE II - LINE 6"			
	FOOT	LOCATION	DIR	REMARKS
	10487	600+82 TO 1020+30	EB	WHITE SKIP DASH
	10487	1020+30 TO 600+82	WB	WHITE SKIP DASH
TOTAL	20,974			
78100100	RAISED REFLECTIVE PAVEMENT MARKER (DOUBLE LANE MARKERS)			
	EACH	LOCATION	DIR	REMARKS
	306	600+82 TO 723+05	EB	ONE-WAY CRYSTAL MARKER
	738	724+96 TO 1020+30	EB	ONE-WAY CRYSTAL MARKER
	738	1020+30 TO 724+96	WB	ONE-WAY CRYSTAL MARKER
	306	723+05 TO 600+82	WB	ONE-WAY CRYSTAL MARKER
TOTAL	2,088			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL			
	EACH	LOCATION	DIR	REMARKS
	153	600+82 TO 723+05	EB	
	369	724+96 TO 1020+30	EB	
	369	1020+30 TO 724+96	WB	
	153	723+05 TO 600+82	WB	
TOTAL	1,044			
A2002914	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 1-3/4" CALIPER, BALLED AND BURLAPPED			
	EACH	LOCATION	DIR	REMARKS
	53	VAR		
TOTAL	53			
A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED			
	EACH	LOCATION	DIR	REMARKS
	52	VAR		
TOTAL	52			
A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED			
	EACH	LOCATION	DIR	REMARKS
	52	VAR		
TOTAL	52			
X0320157	CLEANING UNDERDRAIN OUTLETS			
	EACH	LOCATION	DIR	REMARKS
	320	605+50 TO 1029+09	BOTH	EVERY 500' INCL THE FOLLOWING STA (INSIDE & OUTSIDE SHOULDERS)
	4	663+00	BOTH	INSIDE & OUTSIDE SHOULDERS
	4	729+00	BOTH	INSIDE & OUTSIDE SHOULDERS
	4	786+50	BOTH	INSIDE & OUTSIDE SHOULDERS
	4	836+00	BOTH	INSIDE & OUTSIDE SHOULDERS
	4	916+63	BOTH	INSIDE & OUTSIDE SHOULDERS
	4	996+50	BOTH	INSIDE & OUTSIDE SHOULDERS
	4	1029+09	BOTH	INSIDE & OUTSIDE SHOULDERS
TOTAL	348			
X7010410	SPEED DISPLAY TRAILER			
	CAL MO	LOCATION	DIR	REMARKS
	8		EB	
	8		WB	
TOTAL	16			
X7800070	GROOVING FOR RECESSED PAVEMENT MARKINGS 5"			
	FOOT	LOCATION	DIR	REMARKS
	12223	600+82 TO 723+05	EB	YELLOW EDGE LINE
	12223	600+82 TO 723+05	EB	WHITE EDGE LINE
	29534	724+96 TO 1020+30	EB	YELLOW EDGE LINE
	29534	724+96 TO 1020+30	EB	WHITE EDGE LINE
	29534	1020+30 TO 724+96	WB	YELLOW EDGE LINE
	29534	1020+30 TO 724+96	WB	WHITE EDGE LINE
	12223	723+05 TO 600+82	WB	YELLOW EDGE LINE
	12223	723+05 TO 600+82	WB	WHITE EDGE LINE
TOTAL	167,028			
X7800074	GROOVING FOR RECESSED PAVEMENT MARKINGS 7"			
	FOOT	LOCATION	DIR	REMARKS
	3056	600+82 TO 723+05	EB	WHITE SKIP DASH
	7384	724+96 TO 1020+30	EB	WHITE SKIP DASH
	7384	1020+30 TO 724+96	WB	WHITE SKIP DASH
	3056	723+05 TO 600+82	WB	WHITE SKIP DASH
TOTAL	20,879			
Z0028415	GEOTECHNICAL REINFORCEMENT			
	FOOT	LOCATION	DIR	REMARKS
	173	VAR		AS NEEDED TO REPLACE POOR SUBGRADE UNDER PATCHES
	173			
Z0008758	AERIAL SPEED CHECK MARKING			
	FOOT	LOCATION	DIR	REMARKS
	36	879+74 TO 892+94	EB	IT WILL BE NECESSARY TO HAVE A REPRESENTATIVE OF THE STATE POLICE PRESENT SO THAT THE ACCURACY OF THE MEASUREMENT CAN BE ATTESTED TO IN COURT
	36	879+74 TO 866+54	WB	
TOTAL	72			