

HOT-MIX ASPHALT SCHEDULE

40600285
X4060119

EASTBOUND	BEGIN	END	LENGTH (ft)	POLYMERIZED BIT. MATERIALS (PRIME COAT) (lbs.) (2 APPL.)	HMA SURFACE REMOVAL 1 3/4" (sq yd)	HMA SURFACE REMOVAL 4" (sq yd)	HMA SURFACE REMOVAL (VARIABLE DEPTH) (sq yd)	TEMPORARY RAMPS (sq yd)	2" POLYMERIZED LEVELING BINDER (MM), N90 (ton)	2" POLYMERIZED HMA SURFACE COURSE, SMA, N80 (ton)	
BEGIN JOB	1020+30	1021+35	105	189		280		25	21	29	
	1021+35	1022+48	113	203					34	34	
	1022+48	1028+48	600	1080	1600				179	179	
Transition to 3 lanes	1028+48	1031+18	270	608	900				101	101	
3 Lanes	1031+18	1041+08	990	2673	3960				444	444	
	1041+08	1042+61	153	413	612			25	21	64	
Bridge Omission	1042+61	1045+80	319								
	1045+80	1047+33	153	275	408			25	21	43	
	1047+33	1050+61	328	590	875				98	98	
	1050+61	1052+14	153	275	408			25	21	43	
Bridge Omission	1052+14	1057+23	509								
	1057+23	1058+76	153	275	408			25	21	43	
	1058+76	1067+24	848	1526	2261				253	253	
3 Lanes	1067+24	1085+63	1839	4965	7356				824	824	
Transition to 2 lanes	1085+63	1091+13	550	1238	1833				205	205	
	1091+13	1099+36	823	1481	2195				246	246	
	1099+36	1100+49	113	203					34	34	
(1101+01) 1500E/Conc Med	1100+49	1115+40	1491	2684		3976			445	445	
	1115+40	1116+53	113	203					34	34	
	1116+53	1159+64	4311	7760	11496				1288	1288	
	1159+64	1160+77	113	203					34	34	
1600E (1161+63)	1160+77	1161+93	116	209					35	35	
	1161+93	1163+06	113	203					34	34	
	1163+06	1253+07	9001	16202	24003				2688	2688	
	1253+07	1254+60	153	275	408			25	21	43	
Bridge Omission	1254+60	1256+83	223								
	1256+83	1258+36	153	275	408			25	21	43	
	1258+36	1315+73	5737	10327	15299				1713	1713	
	1315+73	1317+26	153	275	408			25	21	43	
Bridge Omission	1317+26	1318+51	125								
	1318+51	1320+04	153	275	408			25	21	43	
	1320+04	1421+47	10143	18257	27048				3029	3029	
	1421+47	1422+60	113	203					34	34	
(1423+29) 2100E/Conc Med	1422+60	1434+45	1185	2133		3160			354	354	
	1434+45	1435+58	113	203					34	34	
	1435+58	1462+67	2709	4876	7224				809	809	
	1462+67	1463+80	113	203					34	34	
Atkinson Rd (1464+48)	1463+80	1465+07	127	229					38	38	
	1465+07	1466+20	113	203					34	34	
	1466+20	1535+05	6885	12393	18360				2056	2056	
	1535+05	1536+18	113	203					34	34	
Concrete Median (1541+00)	1536+18	1545+82	964	1735					288	288	
	1545+82	1546+95	113	203					34	34	
	1546+95	1556+46	951	1712	2536				284	284	
	1556+46	1557+59	113	203					34	34	
2350E (1558+25)	1557+59	1558+94	135	243					40	40	
	1558+94	1560+07	113	203					34	34	
	1560+07	1608+32	4825	8685	12867				1441	1441	
	1608+32	1609+85	153	275	408			25	21	43	
Bridge Omission	1609+85	1613+65	380								
	1613+65	1615+18	153	275	408			25	21	43	
	1615+18	1647+05	3187	5737	8499				952	952	
	1647+05	1648+18	113	203					34	34	
2500E (1649+11)	1648+18	1649+40	122	220					36	36	
	1649+40	1650+53	113	203					34	34	
	1650+53	1751+80	10127	18229	27005				3025	3025	
	1751+80	1753+33	153	275	408			25	21	43	
Bridge Omission	1753+33	1755+67	234								
	1755+67	1757+00	133	239				25	40	40	
Concrete Median (1761+78)	1757+00	1766+56	956	1721					286	286	
	1766+56	1767+69	113	203					34	34	
	1767+69	1791+47	2378	4280	6341				710	710	
	1791+47	1792+60	113	203					34	34	
IL 78 (1793+31)	1792+60	1793+88	128	230					38	38	
	1793+88	1795+01	113	203					34	34	
	1795+01	1873+34	7833	14099	20888				2339	2339	
	1873+34	1874+47	113	203					34	34	
2900E (1875+23)	1874+47	1875+68	121	218					36	36	
	1875+68	1876+81	113	203					34	34	
	1876+81	1928+43	5162	9292	13765				1542	1542	
END JOB	1928+43	1929+96	153	275	408			25	21	43	
EB TOTAL:				163570	221411	14888	6027	345	26814	27103	
							20034105	MATERIAL TRANSFER DEVICE:			53917

△ REVISED ON 10/22/11

FILE NAME *	USER NAME * grantp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	HOT-MIX ASPHALT SCHEDULE	F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pwwork\grantp\103190281\02200	11-ehs-schedule.dgn	DRAWN -	REVISED -			80	*	HENRY	80	26	
Default	PLOT SCALE * 100.000 / 1/2	CHECKED -	REVISED -			SCALE:		SHEET OF SHEETS		STA.	TO STA.
	PLOT DATE * Thu Aug 21 13:00:00 2014	DATE -	REVISED -					ILLINOIS FED. AID PROJECT		CONTRACT NO. 64664	

* 137-4.5.6) RS-2