

SUMMARY OF QUANTITIES

CONSTR. CODE
90% FEDERAL
10% STATE

PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0005 RURAL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	98	98
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	102	102
20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25
* 25000210	SEEDING, CLASS 2A	ACRE	1.25	1.25
* 25100125	MULCH, METHOD 3	ACRE	1.00	1.00
* 25100630	EROSION CONTROL BLANKET	SQ YD	1,500	1,500
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	265	265
28000305	TEMPORARY DITCH CHECKS	FOOT	48	48
28000400	PERIMETER EROSION BARRIER	FOOT	253	253
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	44	44
40600537	LEVELING BINDER (HAND METHOD), IL-9.5FG, N70	TON	504	504
40600839	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N70	TON	1,424	1,424
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	54,537	54,537
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	11,459	11,459

*SPECIALTY ITEMS

(37-4.5.6) RS-2

FILE NAME *	USER NAME * grnspn	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw_work\pudot\grnspn\02318501\0200	11-shr-schedule.dgn	DRAWN -	REVISED -					80	*	HENRY	80	5
Default	PLOT SCALE * 100.000' / in.	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 64064	
	PLOT DATE * Thu Aug 21 13:25:32 2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							