

SHOULDER SCHEDULE

EASTBOUND SHOULDER (10' unless otherwise noted)	BEGIN	END	LENGTH (ft)	40600982	44000165	X4401198	X4060110	X4060110	40603310	40603310	48203100	48102100
				HMA SURFACE REMOVAL - BUTT JOINT (sq yd)	HMA SURFACE REMOVAL 4" (sq yd)	HMA SURFACE REMOVAL (VARIABLE DEPTH) (sq yd)	BITUMINOUS MATERIALS (PRIME COAT) (lbs.) (2 APPL.)	BITUMINOUS MATERIALS (PRIME COAT) (lbs.) (1 APPL.)	2.25" HMA SURFACE COURSE, MIX C, N50 (ton)	2" HMA SURFACE COURSE, MIX C, N50 (ton)	2" HMA SHOULDERS (ton)	AGGREGATE SHOULDER, TYPE B (ton)
	1613+65	1615+18	153	170				77	20			10
	1615+18	1647+05	3187					1594	446			203
2500E	1647+05	1648+18	113			126	85			14	14	7
	1648+18	1649+40	122		136		92			15	15	8
	1649+40	1650+53	113			126	85			14	14	7
	1650+53	1751+80	10127					5064	1418			646
Bridge Omission	1751+80	1753+33	153	170				77	20			10
	1753+33	1755+67	234									
Concrete Median	1755+67	1757+00	133		148		100			17	17	8
	1757+00	1766+56	956		1062		717			119	119	61
	1766+56	1767+69	113			126	85			14	14	7
Omission for Ramp Gore = 0 - 18' wide	1767+69	1779+87	1218					609	171			78
	1779+87	1783+00	313									
IL 78	1783+00	1785+02	202					91	25			
	1785+02	1791+47	645					323	90			41
	1791+47	1792+60	113			126	85			14	14	7
	1792+60	1793+88	128		142		96			16	16	8
Gore = 18' - 0 Omission for Ramp	1793+88	1795+01	113			126	85			14	14	7
	1795+01	1803+78	877					439	123			56
	1803+78	1807+47	369					166	46			
	1807+47	1812+11	464									
2900E	1812+11	1873+34	6123					3062	857			391
	1873+34	1874+47	113			126	85			14	14	7
	1874+47	1875+68	121		134		91			15	15	8
	1875+68	1876+81	113			126	85			14	14	7
END JOB	1876+81	1928+43	5162					2581	723			329
	1928+43	1929+96	153	170				77	21			10
EB SUBTOTAL:				1915.0	6203.3	2511.1	5882.3	38965.0	10898.8	976.0	976.0	5450.2

• (37-4,5,6) RS-2

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SHOULDER SCHEDULE				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	c:\pwork\pwork\grantpm\0310501\0200711-sh-t-schedule.dgn	DRAWN -	REVISED -		80	*	HENRY	80	31				
	PLOT SCALE = 100.000' / in.	CHECKED -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.				CONTRACT NO. 64664				
	PLOT DATE = Thu Aug 21 13:08:15 2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								