

PATCHING SCHEDULE

12 FEET LANE WIDTH

STATION	LENGTH OF PATCH		44201043		44201047		44201048		44213200	44201299	44213204	44213100
	LT LANE	RT LANE	TYPE 2		TYPE 3		TYPE 4		SAW CUTS	DOWEL	TIE	PAVEMENT
	(feet)	(feet)	(yd ²)	(yd ²)	(yd ²)	(yd ²)	(yd ²)	(yd ²)	(3W+?L) (feet)	BARS, 1.5" (each)	BARS, 3/4" (each)	FABRIC (yd ²)
WEST BOUND:												
1103+00	1104+15	115						153.3	266	20	57	153.3
1106+20	1107+18	98						130.7	232	20	48	130.7
1178+46	1178+58	12				16.0			60	20		16.0
1254+39	1254+49	10		13.3					56	20		
1316+93	1317+33	40						53.3	116	20	19	53.3
1327+35	1327+53	18				24.0			72	20		24.0
1353+04	1353+14	10		13.3					56	20		
1409+20	1409+38	18				24.0			72	20		24.0
1514+49	1514+59	10		13.3					56	20		
1578+82	1578+96	14				18.7			64	20		18.7
1609+06	1609+48	42						56.0	120	20	20	56.0
1613+91	1614+91	100						133.3	236	20	49	133.3
1615+90	1616+92	102						136.0		20	50	136.0
1616+62	1617+62	100					133.3		236	20	49	133.3
1666+55	1666+76	21						28.0	78	20	10	28.0
1668+19	1668+29	10		13.3					56	20		
1695+91	1696+06	15				20.0			66	20		20.0
1720+61	1720+71	10		13.3					56	20		
1744+98	1745+06	8		10.7					52	20		
1745+89	1745+99	10		13.3					56	20		
1791+42	1792+32	90						120.0	216	20	44	120.0
1794+12	1797+12	300						400.0	636	20	149	400.0
1841+01	1841+21	20						26.7	76	20	9	26.7
1873+52	1874+20	68						90.7	172	20	33	90.7
1874+57	1875+25	68						90.7	172	20	33	90.7
1875+43	1877+06	163						217.3	362	20	81	217.3
1878+80	1878+95	15				20.0			66	20		20.0
1928+71	1928+77	6		8.0					48	20		
EAST BOUND:												
1316+89	1317+15	26						34.7	88	20	12	34.7
1319+24	1319+49	25						33.3	86	20	12	33.3
1486+69	1486+75	6	6	8.0	8.0				131.3	40		
1504+52	1504+58	6	6	8.0	8.0				259.3	40		
1662+64	1662+74	10		13.3					56	20		
1765+65	1765+76	11		14.7					58	20		
1766+70	1766+82	12				16.0			60	20		16.0
1767+38	1767+88	50						66.7	136	20	24	66.7
1780+64	1780+79	15	15			20.0	20.0		87	40		40.0
1791+89	1794+03	214						285.3	464	20	106	285.3
1804+28	1804+40	12					16.0		60	20		16.0
1874+16	1874+28	12					16.0		60	20		16.0
1875+94	1876+19	25						33.3	86	20	12	33.3
1877+11	1877+23	12					16.0		60	20		16.0
1928+80	1928+92	12					16.0		60	20		16.0
SUBTOTALS:			16.0	142.7	20.0	222.7	133.3	2089.3	5505.7	920.0	817.0	2465.3
TOTAL:			159		243		2,223		5,506	920	817	2,465

• (37-4,5,6) RS-2

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\grantpm\0310501\020011-shit-schedule.dgn		DRAWN -	REVISED -			80	*	HENRY	80	36	
Default	PLOT SCALE = 200.000' / in.	CHECKED -	REVISED -			CONTRACT NO. 64064					
	PLOT DATE = Fri Aug 22 08:56:52 2014	DATE -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO

ILLINOIS FED. AID PROJECT