

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	HSIP 90% FED 10% STATE 0004
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
* 72000100	SIGN PANEL - TYPE 1	SQ FT	48	48
* 72000200	SIGN PANEL - TYPE 2	SQ FT	35	35
* 78009000	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	250	250
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	21,675	21,675
* 78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	2,198	2,198
* 78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	723	723
* 78009024	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	117	117
* 78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	295	295
* 80500100	SERVICE INSTALLATION, TYPE A	EACH	1	1
* 81028740	UNDERGROUND CONDUIT, COILABLE, COILABLE NONMETALLIC CONDUIT 1 1/2" DIA.	FOOT	80	80
* 81028760	UNDERGROUND CONDUIT, COILABLE, COILABLE NONMETALLIC CONDUIT 2 1/2" DIA.	FOOT	97	97
* 81028790	UNDERGROUND CONDUIT, COILABLE, COILABLE NONMETALLIC CONDUIT 4" DIA.	FOOT	297	297
* 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	3	3
* 81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1	1
* 81603035	UNIT DUCT, 600V, 2-1C No. 6 1/C No. 6 GROUND, (XLP-TYPE USE) 1" DIA., POLYETHYLENE	FOOT	913	913
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) 1/C NO. 10	FOOT	1760	1,760
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	9	9
* 82500335	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240 VOLT, 100 AMP	EACH	1	1
* 83003600	LIGHT POLE, ALUMINUM, 45 FT. MH., 15 FT. DAVIT ARM	EACH	5	5
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	30	30
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	5	5
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	1
* 86200200	UNINTERRUPTIBLE POWER SUPPLY, STANDARD	EACH	1	1

* SPECIALTY ITEMS
 ▲ 100% STATE

FILE NAME :	USER NAME : cushmanb	DESIGNED :	REVISED :	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
o:\p\work\p\idat\cushmanb\10333009\021709-sht-schedule.dgn		DRAWN :	REVISED :			*	2R-1	HENRY	235	6
PLOT SCALE * 100.0000 / 1" = 100'		CHECKED :	REVISED :		SCALE:	SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 64J43		
PLOT DATE * Wed Aug 06 08:56:39 2014		DATE :	REVISED :		ILLINOIS FED. AID PROJECT					

* 5789 & 5861

Rev.