

80% FED. / 20% STATE
CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY 0004 RURAL	BRIDGE 0014 RURAL
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD	27.2		27.2
50200100	STRUCTURE EXCAVATION	CU YD	96		96
50300225	CONCRETE STRUCTURES	CU YD	40.4		40.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	276		276
50300260	BRIDGE DECK GROOVING	SQ YD	628		628
50300300	PROTECTIVE COAT	SQ YD	837		837
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	3276		3276
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	69840		69840
50800515	BAR SPLICERS	EACH	710		710
51500100	NAME PLATES	EACH	1		1
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12		12
52100510	ANCHOR BOLTS, 3/4"	EACH	24		24

14
* SPECIALTY ITEMS

FILE NAME *	USER NAME = oarpenterdj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr:\pwork\psidot\oarpenterdj\d8183264\	366417-ehv-S00.dgn	DRAWN -	REVISED -					613	(BD BR)BR	BUREAU	63	5
	PLOT SCALE = 1/8" = 1'-0"	CHECKED -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 66A17	
	PLOT DATE = 8/6/2014	DATE -	REVISED -	ILLINOIS FED. AID PROJECT								