

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	RURAL BRIDGE
				0004 RURAL	0014 053-0157
50102400	CONCRETE REMOVAL	CU YD	18.3		18.3
50105220	PIPE CULVERT REMOVAL	FOOT	12	12	
50300225	CONCRETE STRUCTURES	CU YD	33.3		33.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	245.7		245.7
50300260	BRIDGE DECK GROOVING	SQ YD	490		490
50300300	PROTECTIVE COAT	SD YD	521		521
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	79,670		79,670
50800515	BAR SPLICERS	EACH	588		588
50901050	STEEL RAILING, TYPE SM	FOOT	280		280
51500100	NAME PLATES	EACH	1		1
60100080	FRENCH DRAINS	CU YD	2	2	
60100085	GEOTECHNICAL FABRIC FOR FRENCH DRAINS	SQ YD	17	17	
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	25	25	
*63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	

14

\* SPECIALTY ITEMS

FILE NAME *	USER NAME = lukkaridp	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
at\pvc\work\pvc\dot\lukkaridp\02179226\0366A18-shr-SOQ.dgn		DRAWN -	REVISED -		370	HOZ BR BR	LIVINGSTON	65	5				
PLOT SCALE * 1/8" = 1'-0"		CHECKED -	REVISED -		SCALE: SHEET NO. 3 OF 3 SHEETS STA. TO STA.				CONTRACT NO. 66A18				
PLOT DATE * 8/14/2014		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								

Key.