

MAINLINE SCHEDULE												
STA	TO	STA	LENGTH	WIDTH	AREA	1 1/2" HMA SURFACE COURSE "C" N50	LEVELING BINDER (MACH. METH.) IL-9.5FG, N50	BIT MATLS PRIME COAT	MIXTURE FOR CRACKS JOINTS, & FLANGWAYS	HMA SURFACE REMOVAL 2 1/4"	HMA STABILIZ. 6" AT SPBGR	LEVELING BINDER (HAND. METH.) N50
			FT	FT	SQ YD	TON	TON	POUND	TON	SQ YD	SQ YD	TON
STAGE I												
45+00	TO	46+62	162.00	11	198.0	16.6	8.3	133.7	0.059	198.0		0.10
46+62	TO	48+07	145.00	14	225.6	18.9	9.6	154.7	0.068	225.6		0.11
48+07	TO	48+43	36.00	14	56.0					56.0		
49+51	TO	49+87	36.00	14	56.0					56.0		
49+87	TO	51+47	160.00	14	248.9	20.9	11.0	172.6	0.075	248.9		0.12
47+20	TO	48+31	111.00	VAR	52.8						52.8	
49+69	TO	50+80	111.00	VAR	55.0						55.0	
STAGE II												
45+00	TO	46+63	163.00	11	199.2	16.7	8.4	134.5	0.060	199.2		0.10
46+63	TO	48+07	144.00	14	224.0	18.8	9.6	153.7	0.067	224.0		0.11
48+07	TO	48+43	36.00	14	56.0					56.0		
49+51	TO	49+87	36.00	14	56.0					56.0		
49+87	TO	51+47	160.00	14	248.9	20.9	11.0	172.6	0.075	248.9		0.12
47+14	TO	48+25	111.00	VAR	52.8						52.8	
49+63	TO	50+73	110.00	VAR	55.0						55.0	
TOTAL					1784	113	58	922	0.40	1569	216	0.7

TREE REMOVAL SCHEDULE			
STA	OFFSET	DIAMETER	DIAMETER
		6-15 UNIT	OVER 15 UNIT
47+04	41' RT		18
47+68	53' RT	8	
46+53	48' LT	6	
46+53	48' LT	7	
46+58	42' LT	9	
46+61	41' LT	12	
46+64	45' LT	7	
46+81	50' LT	8	
46+83	54' LT	12	
46+89	50' LT	10	
46+94	49' LT	6	
47+10	40' LT	9	
47+12	40' LT	11	
47+17	42' LT	7	
47+35	43' LT	15	
47+35	49' LT	12	
47+51	49' LT	11	
47+59	52' LT	15	
47+62	41' LT	9	
47+64	42' LT	10	
47+81	46' LT	12	
47+89	45' LT	6	
50+49	34' LT	13	
50+51	34' LT	14	
50+73	37' LT	12	
50+79	36' LT	7	
50+92	32' LT	7	
51+01	31' LT		16
51+14	33' LT	7	
51+15	32' LT	12	
51+16	32' LT	7	
TOTAL		281	34

PAVEMENT MARKING SCHEDULE											
STA	TO	STA	LINE TYPE	PAINT PVMT MARKING			TEMPORARY PVMT MARKING			WORK ZONE PAVT MK REM SQ FT	PAVT MARKING REM SQ FT
				4"	6"	6"	4"	6"	24"		
				WHITE FOOT	YELLOW FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT	WHITE FOOT		
STAGE I											
45+42	TO	52+81					837	246	22	323	138
STAGE II											
45+15	TO	52+40					841	246	22	324	84
PERMANENT PAVEMENT MARKINGS											
45+00	TO	51+47	EDGE LINE	2588							
45+00	TO	47+24	EB NO-PASSING LINE AND CENTERLINE		448	100					
47+24	TO	50+42	EB/WB NO-PASSING LINE		1272						
50+42	TO	51+47	WB NO-PASSING LINE AND CENTERLINE		210	40					
TOTAL				4518	140	1678	492	44	647	222	

PAINT PAVEMENT MARKING QUANTITIES ARE FOR TWO APPLICATIONS.
6" WHITE TEMPORARY PAVEMENT MARKING INCLUDED IN COST OF TEMPORARY CONCRETE BARRIER.

PAVEMENT REMOVAL SCHEDULE			
STA TO STA	PAVEMENT REMOVAL (SPECIAL)	PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL
	SQ YD	SQ YD	SQ YD
48+06.48 TO 48+36.48		73.3	20
48+36.48 TO 48+42.48	19.3		
49+51.06 TO 49+57.06	19.3		
49+57.06 TO 49+87.06		73.3	20
TOTALS		39	147