

PLOT DATE =

REVISED

CHECKED -

VPT

SHEET NO. 3 OF

Bar	No.	Size	Length	Shape	
a	44	#7	25'-0"		
01	44	#7	23'-4"		
d	46	#4	4'-6"		
dı	112	#4	1'-2"		
h	248	#4	5′-8″		
hз	48	#6	8'-0"		
h4	48	#6	11'-8"		
h5	10	#6	22'-3"		
V	92	#6	6′-4″		
VI	16	#4	9′-3″		
Concrete Box Culverts			Cu. Yd.	39.2	
Reinforcement Bars			Pound	8240	

ETAILS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
. 047–2030	326	(109, 110)R-1	KENDALL	619	382	
			CONTRACT	NO. 6	6B84	
4 SHEETS	ILLINOIS FED. AID PROJECT					