

SUMMARY OF QUANTITIES					
CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE		
			TOTAL QUANTITY	RDWY 0004 RURAL	038-0119 (EX.) 038-2026 (PR.) BRIDGE 0011 RURAL
20200100	EARTH EXCAVATION	CU YD	278	278	
20400800	FURNISHED EXCAVATION	CU YD	309	309	
20700110	POROUS GRANULAR EMBANKMENT	TON	855		855
25000210	SEEDING, CLASS 2A	ACRE	0.42	0.42	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	37	37	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	37	37	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	37	37	
25100115	MULCH, METHOD 2	ACRE	0.42	0.42	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	166	166	
28000305	TEMPORARY DITCH CHECKS	FOOT	134	134	
28000500	INLET AND PIPE PROTECTION	EACH	4	4	
28100107	STONE RIPRAP, CLASS A4	50 YD	246		246
28200200	FILTER FABRIC	50 YD	246		246
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	50 YD	267	267	

14