

GUARDRAIL SCHEDULE											
LOCATION	LANE	SIDE	GUARD RAIL REMOVAL FOOT	CURB REMOVAL FOOT	TRAF BAR TERM		SPBGR TYPE A 6' POSTS FOOT	CONC CURB TYPE B FOOT	HMA SHLDS 6" FOR SPBGR STABILIZATION SQ YD	TERM MARK DIRECT APPLIED EACH	GUARDRAIL MARKER EACH
					TYPE 6 EACH	TYPE 1 SPEC (TANG) EACH					
SN 038-0123											
STA. 129+39.5 - STA. 131+60.9	NB	DRIVE	288	30	1	1	128.125	15	85.3	1	3
STA. 127+26.9 - STA. 130+01	SB	DRIVE	291	30	1	1	178.125	15	101.6	1	3
SN 038-0125											
STA. 260+48 - STA. 262+97	NB	DRIVE	290	30	1	1	153.125	15	90	1	3
STA. 257+98.3 - STA. 260+47	SB	DRIVE	290	30	1	1	153.125	15	90.1	1	3
TOTALS			1159	120	4	4	612.5	60	367	4	12

TEMPORARY PAVEMENT MARKING				
LOCATION STA. TO STA.	TEMPORARY			SHORT TERM PAVT MARK FOOT
	4"		6"	
	WHITE FOOT	YELLOW FOOT	WHITE FOOT	
STAGE 1				
NORTHBOUND				
BEGINNING TAPER	400	1500		
TANGENT	19225	19225		
ENDING TAPER	180			
SOUTHBOUND				
BEGINNING TAPER	400	1500		
TANGENT	19225	19225		
ENDING TAPER	180			
STAGE 2				
NORTHBOUND				
BEGINNING TAPER	175	1167		
TANGENT	19225	19225		
ENDING TAPER	60			
SOUTHBOUND				
BEGINNING TAPER	175	1167		
TANGENT	19225	19225		
ENDING TAPER	60			
BEFORE FINAL LIFT				
CENTERLINE				
NORTHBOUND			4670	748
SOUTHBOUND			4670	748
EDGELINES				
NORTHBOUND	19225	19225		
SOUTHBOUND	19225	19225		
RAMPS				
EDGELINE	8186	4318		
TOTALS	250168	9340		1496

SEEDING						
LOCATION STA TO STA	SEEDING CLASS 2 ACRE	MULCH METHOD 2 ACRE	EROSION CONTROL BLANKET SQ YD	NITROGEN FERTILIZER NUTRIENT POUND	PHOSPHORUS FERTILIZER NUTRIENT POUND	POTASSIUM FERTILIZER NUTRIENT POUND
MAINLINE						
100+00 - 122+31	0.13	0.13		12	12	12
122+31 - 145+94	0.92	0.92		83	83	83
145+94 - 185+42	0.93	0.93		84	84	84
185+42 - 244+54	1.34	1.34		121	121	121
244+54 - 286+75	1.78	1.78		160	160	160
RAMP A						
	0.72	0.72		65	65	65
RAMP B						
	0.75	0.75		68	68	68
RAMP C						
	1.00	1.00		90	90	90
RAMP D						
	0.64	0.64		58	58	58
126+92 - 129+82 SB			340			
129+54 - 131+91 NB			470			
165+00 SB			85			
191+00 SB			61			
191+00 NB			75			
231+00 SB			78			
257+64 - 260+30 SB			489			
260+66 - 263+30 NB			373			
TOTAL	8.21	8.21	1971	739	739	739

HIGH TENSION CABLE MEDIAN BARRIER (HTCMB)					
LOCATION STATION TO STATION	SIDE	HTCMB FOOT	HTCMB TERMINAL EACH	REMOVE HTCMB FOOT	REMOVE HTCMB TERMINAL EACH
184+40 TO 193+90	SB			850	2
184+40 TO 193+75	SB	835	2		
MAINTENANCE CROSSOVER					
194+85 TO 273+91	SB			7806	2
195+00 TO 273+90	SB	7790	2		
TOTALS		8625	4	8656	4