

| CODE NO. | ITEM  | UNIT  | TOTAL QUANTITY | CONSTR. CODE                                    |
|----------|---|-------|----------------|---|
|          |   |       |                | STATE FUNDS<br>100%<br>ROADWAY<br>0005<br>RURAL |
| 20200100 | EARTH EXCAVATION                                  | CU YD | 83             | 83  |
| 31101000 | SUBBASE GRANULAR MATERIAL, TYPE B                 | TON   | 170            | 170   |
| 42000301 | PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)    | SQ YD | 2096           | 2096  |
| 42001200 | PAVEMENT FABRIC                                   | SQ YD | 2854           | 2854  |
| 44000100 | PAVEMENT REMOVAL                                  | SQ YD | 2096           | 2096  |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL               | FOOT  | 108            | 108   |
| 44004250 | PAVED SHOULDER REMOVAL                            | SQ YD | 758            | 758   |
| 48101200 | AGGREGATE SHOULDERS, TYPE B                       | TON   | 28             | 28  |
| 48300300 | PORTLAND CEMENT CONCRETE SHOULDERS 8"             | SQ YD | 758            | 758   |
| 60608600 | COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 | FOOT  | 108            | 108   |
| 67100100 | MOBILIZATION                                      | L SUM | 1              | 1   |
| 70100100 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701316   | EACH  | 1              | 1   |
| 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201   | L SUM | 1              | 1   |
| 70100455 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701206   | L SUM | 1              | 1   |

|                                       |                         |                         |                         |   |                              |                    |          |            |                 |              |         |
|---------------------------------------|-------------------------|-------------------------|-------------------------|---|------------------------------|--------------------|----------|------------|-----------------|--------------|---------|
| FILE NAME =                           | USER NAME = woodshankr1 | DESIGNED - HASAN AHMED  | REVISED - 6/5/2014 H.A. | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>SUMMARY OF QUANTITIES</b> | F.A.I.<br>RTE.     | SECTION  | COUNTY     | TOTAL<br>SHEETS | SHEET<br>NO. |         |
| c:\pw_work\p\p\p\woodshankr1\d8388272 | 0366073-shr-details.dgn | DRAWN - HASAN AHMED     | REVISED -               |   |                              | 55                 | (53-11K) | LIVINGSTON | 10              | 3            |         |
| *MODELNAME*                           | PLOT SCALE = 1/8"=1'-0" | CHECKED - RON WOODSHANK | REVISED -               |   |                              | CONTRACT NO. 66D73 |          |            |                 |              |         |
|                                       | PLOT DATE = 8/26/2014   | DATE - 5/10/2014        | REVISED -               |   |                              | SCALE:             | SHEET 1  | OF 2       | SHEETS          | STA.         | TO STA. |