

LOCATION OF WORK:

S.N. 057-0256

FAP 730 (US 51 BUS)

FAP 730 (US 51 BUS)

URBAN MULTILANE

URBAN MULTILANE

URBAN MULTILANE

OTHER PRINCIPAL ARTERIAL

OTHER PRINCIPAL ARTERIAL

OTHER PRINCIPAL ARTERIAL

STA. 196+92.19 TO STA. 198+50.68

STA. 195+16.00 TO STA. 199+76.40

STA. 195+16.00 TO STA. 199+76.40

MCLEAN COUNTY

MCLEAN COUNTY

MCLEAN COUNTY

FUNDING BREAKOUT:

80% FEDERAL

80% FEDERAL

100% BLOOMINGTON-NORMAL

20% STATE

20% STATE

WATER RECLAMATION DISTRICT

CONSTRUCTION TYPE CODE:

0011

0004

0043

CODE NO.	ITEM	UNIT	TOTAL QUANTITY			
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	180.0	0.0	180.0	0.0
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	61.0	0.0	61.0	0.0
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	560.0	0.0	560.0	0.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	500.0	0.0	500.0	0.0
40600990	TEMPORARY RAMP	SQ YD	130.0	0.0	130.0	0.0
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	110.0	0.0	110.0	0.0
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	90.0	0.0	90.0	0.0
40800025	BITUMINOUS MATERIALS (PRIME COAT)	POUND	10.0	0.0	10.0	0.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	5.0	0.0	5.0	0.0
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	43.0	0.0	43.0	0.0
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	100.0	0.0	100.0	0.0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,454.0	0.0	1,454.0	0.0
42400800	DETECTABLE WARNINGS	SQ FT	49.0	0.0	49.0	0.0
44000100	PAVEMENT REMOVAL	SQ YD	481.0	0.0	481.0	0.0

• DENOTES SPECIALTY ITEM

FILE NAME *	USER NAME * hoganbj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\p\work\p\dot\hoganbj\02379563\0577	48-hat(223-029-500.dgn)	DRAWN -	REVISED -		730	62-ZBR	MCLEAN	65	4				
#MODELNAME*	PLOT SCALE * 48.0000 ' / in.	CHECKED -	REVISED -		SCALE: SHEET 2 OF 8 SHEETS STA. TO STA.				CONTRACT NO. 70540				
	PLOT DATE * 8/12/2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								