

LOCATION				PAVEMENT MARKING SCHEDULE												
				PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS & SYMBOLS	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	RAISED REFLECTIVE PAVEMENT MARKER	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	GROOVING FOR RECESSED PAVEMENT MARKING 5"	GROOVING FOR RECESSED PAVEMENT MARKING 7"	GROOVING FOR RECESSED PAVEMENT MARKING 13"	
LT/RT	STA	TO	STA	78003100 SQ FT	78009004 FOOT	78009006 FOOT	78009012 FOOT	78100100 EACH	78300100 SQ FT	78300200 EACH	78004210 FOOT	78100105 EACH	X7830070 FOOT	X7830074 FOOT	X7830078 FOOT	
STAGE 1	200+02.7		204+31.6						35.7							
STAGE 2	196+92.2		198+50.7		39.6							2.0	39.6			
CL	195+00.0		196+92.2					4.0		4.0	70.9					
	198+50.7		203+00.0													
X - WALK	199+58.0		199+64.0			95.3	141.2		64.5					95.3	141.2	
X - WALK	199+71.5		200+05.7			62.2	91.8		110.0					62.2	91.8	
	196+35.3			12.5												
	199+35.3			12.5												
	195+16.0		199+58.0		442.0								442.0			
TOTAL				25.0	481.6	157.5	233.0	4.0	210.2	4.0	70.9	2.0	481.6	157.5	233.0	
ROUND TO				25.0	490.0	158.0	233.0	4.0	220.0	4.0	80.0	2.0	490.0	158.0	233.0	

SEEDING AND EROSION CONTROL SCHEDULE													
LOCATION				SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 2	SODDING	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECK	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION
LT/RT	STA	TO	STA	25000350 ACRE	25000400 POUND	25000500 POUND	25000600 POUND	25100115 ACRE	25200100 SQ YD	28000250 POUND	28000305 FOOT	28000400 FOOT	28000500 EACH
LT	195+10.1		197+54.1	0.1917	3.8341	3.8341	3.8341	0.1917	309.2	319.42	50	280.5	2.0
RT	195+10.1		195+54.3	0.006693	0.1339	0.1339	0.1339	0.006693	10.8	11.16		38.3	
RT	195+84.9		197+26.5	0.2271	4.5421	4.5421	4.5421	0.2271	366.4	378.5	30.0	178.2	2.0
RT	197+81.9		198+47.0	0.08679	1.7355	1.7355	1.7355	0.08679	140.0	144.65	40.0	85.4	
LT	198+24.3		199+54.3	0.096198	1.924	1.924	1.924	0.096198	155.2	160.33	50.0	144.5	
RT	198+70.2		199+66.0	0.108285	2.1657	2.1657	2.1657	0.108285	174.7	180.48		98.6	
TOTAL				0.716766	14.3353	14.3353	14.3353	0.716766	1156.3	1194.54	170.0	825.5	4.0
ROUND TO				0.75	15.0	15.0	15.0	0.75	1175.0	1250.0	170.0	830.0	4.0

DRAINAGE STRUCTURE SCHEDULE									
STRUCTURE NUMBER	STATION	OFFSET	RIM ELEV.	INVERT ELEV	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, OPEN LID	INLETS, TYPE A, TYPE 11 FRAME AND GRATE
					54213663	54213681	60200105	60223700	60236800
1	195+14.	19.5' LT	758.98	756.73 S, 756.06 SW, MEET EX. NW					1
2	195+18.5	17.6' LT	759.09	756.09 NE					1
3	195+23.5	21.2' LT	759.47	756.8 NW			1		
4	195+86.4	20.6' LT	760.04	756.71 W			1		
5	195+86.4	27.2' RT	759.8	753.21 N, 753.19 S, 756.28 E				1	
6	196+75.	27.2' RT	760.52	752.67 N, 752.57 SW				1	
7	197+34.	33.2' RT	N/A	752.3		1			
8	197+47.9	41.6' LT	N/A	752.4	1				
TOTALS:					1	1	2	2	2

PIPE SCHEDULE						
LOCATION				STORM SEWERS, RUBBER GASKET, CL A, TYPE 1 12"	STORM SEWERS, RUBBER GASKET, CL A, TYPE 2 36"	TRENCH BACKFILL
LT/RT	STA	TO	STA	550A2320 FOOT	550A2600 FOOT	20800150 CU YD
LT	195+18.5		195+14.	3		0.8
LT	195+23.5		195+14.	6.7		1.2
	195+86.4 LT		195+86.4 RT	42.8		8.7
RT	196+75.		197+34.		54.8	48.8
TOTAL				52.5	54.8	59.5
ROUND TO				53.0	55.0	60.0



USER NAME = hoganb	DESIGNED - MRS	REVISED
FILE NAME = \$FILES#	DRAWN - MRS	REVISED
PLOT SCALE = 2.0000' / in.	CHECKED - JBMB	REVISED
PLOT DATE = 8/13/2014	DATE - 1/25/13	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES			
SCALE: N/A	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
730	62-ZBR	MCLEAN	65	15
CONTRACT NO. 70540				
ILLINOIS FED. AID PROJECT				