

LOCATION OF WORK:	FAP 704 (I-55BUSN/VET'S PKWY)	S. N. 057-0063	S. N. 057-0064
	URBAN MULTILANE	URBAN MULTILANE	URBAN MULTILANE
	OTHER PRINCIPAL ARTERIAL	OTHER PRINCIPAL ARTERIAL	OTHER PRINCIPAL ARTERIAL
	STA. 33+30 TO STA. 89+41.79	STA. 47+06.97 TO STA. 49+10.79	STA. 72+79.68 TO STA. 75+96.94
	MCLEAN COUNTY	MCLEAN COUNTY	MCLEAN COUNTY
FUNDING BREAKOUT:	80% FED / 20% STATE	80% FED / 20% STATE	80% FED / 20% STATE
CONSTRUCTION TYPE CODE:	0004	0014	0014

CODE NO.	ITEM	UNIT	TOTAL QUANTITY		
28100107	STONE RIPRAP, CLASS A4	SQ YD	420.0	420.0	0.0
28200200	FILTER FABRIC	SQ YD	420.0	420.0	0.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	15,070.0	15,070.0	0.0
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	52,000	52,000	0.0
40600300	AGGREGATE (PRIME COAT)	TON	135.0	135.0	0.0
40600909	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N90	TON	4,480.0	4,480.0	0.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,060.0	2,060.0	0.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	790.0	790.0	0.0
40600990	TEMPORARY RAMP	SQ YD	1,970.0	1,970.0	0.0
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	7,100.0	7,100.0	0.0
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	785.0	785.0	0.0
42400800	DETECTABLE WARNINGS	SQ FT	245.0	245.0	0.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	45,835.0	45,835.0	0.0
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	575.0	575.0	0.0
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	8,265.0	8,265.0	0.0

• DENOTES SPECIALTY ITEM