

LOCATION OF WORK:

FAP 704 (I-55BUSN/VET'S PKWY)

S. N. 057-0063

S. N. 057-0064

URBAN MULTILANE

URBAN MULTILANE

URBAN MULTILANE

OTHER PRINCIPAL ARTERIAL

OTHER PRINCIPAL ARTERIAL

OTHER PRINCIPAL ARTERIAL

STA. 33+30 TO STA. 89+41.79

STA. 47+06.97 TO STA. 49+10.79

STA. 72+79.68 TO STA. 75+96.94

MCLEAN COUNTY

MCLEAN COUNTY

MCLEAN COUNTY

FUNDING BREAKOUT:

80% FED / 20% STATE

80% FED / 20% STATE

80% FED / 20% STATE

CONSTRUCTION TYPE CODE:

0004

0014

0014

CODE NO.	ITEM	UNIT	TOTAL QUANTITY			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	30.0	30.0	0.0	0.0
44000600	SIDEWALK REMOVAL	SQ FT	785.0	785.0	0.0	0.0
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	8540.0	8540.0		
44004000	PAVED DITCH REMOVAL	FOOT	31.0	31.0	0.0	0.0
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,310.0	1,310.0	0.0	0.0
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	995.0	995.0	0.0	0.0
44213198	TIE BARS 1/2"	EACH	120.0	120.0	0.0	0.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	150.0	150.0	0.0	0.0
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	4,160.0	4,160.0	0.0	0.0
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	5,220.0	5,220.0	0.0	0.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1,430.0	1,430.0	0.0	0.0
50102400	CONCRETE REMOVAL	CU YD	15.4	1.2	7.0	7.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	12.8	0.0	6.2	6.6
50300300	PROTECTIVE COAT	SQ YD	39.0	0.0	17.5	21.5
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,620.0	0.0	820.0	800.0

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = dodgema	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\dodgema\p0267571\0570338-shl-500.dgn		DRAWN -	REVISED -		704	157-71RS-1&1RS-3	McLean	273	9				
MODELNAME#	PLOT SCALE = 48.0000' / in.	CHECKED -	REVISED -		SCALE: SHEET 3 OF 10 SHEETS STA. TO STA.				CONTRACT NO. 70838				
	PLOT DATE = 6/11/2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								