

LOCATION OF WORK:

FAP 704 ( I-55BUSN/VET'S PKWY)

S. N. 057-0063

S. N. 057-0064

URBAN MULTILANE

URBAN MULTILANE

URBAN MULTILANE

OTHER PRINCIPAL ARTERIAL

OTHER PRINCIPAL ARTERIAL

OTHER PRINCIPAL ARTERIAL

STA. 33+30 TO STA. 89+41.79

STA. 47+06.97 TO STA. 49+10.79

STA. 72+79.68 TO STA. 75+96.94

MCLEAN COUNTY

MCLEAN COUNTY

MCLEAN COUNTY

FUNDING BREAKOUT:

80% FED / 20% STATE

80% FED / 20% STATE

80% FED / 20% STATE

CONSTRUCTION TYPE CODE:

0004

0014

0014

CODE NO.	ITEM	UNIT	TOTAL QUANTITY			
50800515	BAR SPLICERS	EACH	44.0	0.0	28.0	16.0
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2.0	2.0	0.0	0.0
54215547	METAL END SECTIONS 12"	EACH	1.0	1.0	0.0	0.0
54248510	CONCRETE COLLAR	CU YD	2.8	2.8	0.0	0.0
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	16.0	16.0	0.0	0.0
54390230	INSERTION CULVERT LINER 36"	FOOT	84.0	84.0	0.0	0.0
60100945	PIPE DRAINS 12"	FOOT	20.0	20.0	0.0	0.0
60261000	INLETS TO BE ADJUSTED WITH NEW TYPE 8 GRATE	EACH	1.0	1.0	0.0	0.0
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	32.0	32.0	0.0	0.0
60500060	REMOVING INLETS	EACH	3.0	3.0	0.0	0.0
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	9.2	9.2	0.0	0.0
60600605	CONCRETE CURB, TYPE B	FOOT	5,270.0	5,270.0	0.0	0.0
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	30.0	30.0	0.0	0.0
60900515	CONCRETE THRUST BLOCKS	EACH	1.0	1.0	0.0	0.0

\* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = dodgene	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RT#	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\dodgene\20267571\0570038-ah1-500.dgn		DRAWN -	REVISED -		704	157-TRS-1&RS-3	McLean	273	10				
#MODELNAME#	PLOT SCALE = 48.0000' / 1"	CHECKED -	REVISED -		SCALE: SHEET 4 OF 10 SHEETS STA. TO STA.				CONTRACT NO. 70838				
	PLOT DATE = 6/11/2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								