

SCHEDULE OF QUANTITIES

EARTH EXCAVATION

LOCATION	EARTH EXCAVATION 20200100 (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	FURNISHED EXCAVATION 20400800 (CU YD)	
RURAL SECTION						
NORTHBOUND:						
I-39 NB LEFT STA. 305+37.00 - 377+00.00	0.0	0.0	289.5	-289.5	289.5	
I-39 NB LEFT STA. 377+00.00 - 549+61.00	0.0	0.0	697.3	-697.3	697.3	
I-39 NB RIGHT STA. 305+19.00 - 377+00.00	0.0	0.0	131.4	-131.4	131.4	
I-39 NB RIGHT STA. 377+00.00 - 549+61.00	0.0	0.0	315.9	-315.9	315.9	
CH 12 RAMP B LEFT	0.0	0.0	0.9	-0.9	0.9	
CH 12 RAMP B RIGHT	0.0	0.0	44.3	-44.3	44.3	
CH 12 RAMP C LEFT	0.0	0.0	0.3	-0.3	0.3	
CH 12 RAMP C RIGHT	0.0	0.0	16.6	-16.6	16.6	
SOUTHBOUND:						
I-39 SB LEFT STA. 305+67.00 - 377+00.00	0.0	0.0	267.3	-267.3	267.3	
I-39 SB LEFT STA. 377+00.00 - 550+04.00	0.0	0.0	648.9	-648.9	648.9	
I-39 SB RIGHT STA. 305+47.00 - 377+00.00	0.0	0.0	249.1	-249.1	249.1	
I-39 SB RIGHT STA. 377+00.00 - 550+04.00	0.0	0.0	602.2	-602.2	602.2	
CH 12 RAMP A LEFT	0.0	0.0	17.1	-17.1	17.1	
CH 12 RAMP A RIGHT	0.0	0.0	0.0	0.0	0.0	
CH 12 RAMP D LEFT	0.0	0.0	41.0	-41.0	41.0	
CH 12 RAMP D RIGHT	0.0	0.0	0.7	-0.7	0.7	
						ROUND TO:
NB RURAL:	0.0	0.0	1496.2	-1496.2	1496.2	1500.0
SB RURAL:	0.0	0.0	1826.3	-1826.3	1826.3	1830.0
GRAND TOTAL:	0.0	0.0	3322.5	-3322.5	3322.5	
ROUNDED TOTAL:	0.0	0.0	3330.0	-3330.0	3330.0	3330.0

NOTES:

1. THE SHRINKAGE FACTOR USED IS 25%.
2. SHRINKAGE, EMBANKMENT, AND BALANCE IS FOR INFORMATION ONLY.
3. NO PAYMENT WILL BE ALLOWED FOR OVERHAUL
4. EXCAVATION REQUIRED FOR PCC BASE COURSE, FULL DEPTH BITUMINOUS PAVEMENT, BITUMINOUS SHOULDERS, BITUMINOUS BASE COURSE AND AGGREGATE SHOULDER IS MEASURED AND PAID FOR AS EARTH EXCAVATION

CHANGEABLE MESSAGE SIGN

LOCATION	CHANGEABLE MESSAGE SIGN X7015005 (CALENDAR DAYS)	
	NB RURAL	SB RURAL
I-39 SB START:		7
I-39 NB START:	7	
CH 12 RAMP B:	7	
CH 12 RAMP D:		7
CH 8 RAMP B:	7	
CH 8 RAMP D:		7
TOTAL:	21	21
TOTAL:	42	

FRAMES AND GRATES TO BE ADJUSTED

LOCATION	STATION	OFFSET		FRAMES AND GRATES TO BE ADJUSTED 60300105 (EACH)	
NB RURAL	CH 12 RAMP B GORE	358+56.00	55.4'	RT	1
NB RURAL	CH 8 RAMP B GORE	515+66.00	39.2'	RT	1
NB RURAL	MEDIAN	516+00.00	2.6'	RT	1
NB RURAL	MEDIAN	521+00.00	2.6'	RT	1
NB RURAL	MEDIAN	526+00.00	2.6'	RT	1
NB RURAL	MEDIAN	531+00.00	2.6'	RT	1
NB RURAL	MEDIAN	536+50.00	2.6'	RT	1
NB RURAL	MEDIAN	542+00.00	2.6'	RT	1
NB RURAL	MEDIAN	547+00.00	2.6'	RT	1
SB RURAL	CH 12 RAMP D GORE	328+94.00	53.5'	LT	1
SB RURAL	CH 12 RAMP A GORE	360+15.00	61.4'	LT	1
SB RURAL	MEDIAN	516+00.00	2.6'	LT	1
SB RURAL	MEDIAN	521+00.00	2.6'	LT	1
SB RURAL	CH 8 RAMP A GORE	521+00.00	38.8'	LT	1
SB RURAL	MEDIAN	526+00.00	2.6'	LT	1
SB RURAL	MEDIAN	531+00.00	2.6'	LT	1
SB RURAL	MEDIAN	536+50.00	2.6'	LT	1
					NB RURAL: 9
					SB RURAL: 8
					TOTAL: 17