

1 2 3 4 5 6 7

CONSTRUCTION CODE  
FEDERAL FUNDS  
90% FED / 10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN														
				6-00166-0000	6-00166-0000	6-00313-0000	6-00166-0000	6-00166-0000	6-00166-0000	6-00166-0000	6-00313-0000							
				ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE							
				0004	0014	0014	0014	0014	0014	0014	0014							
	IL 72	084-0126	084-0142	084-0136	084-0185	084-0127	084-0148	084-0140,0141,0143	0144,0145,0146									
20300100	CHANNEL EXCAVATION	CU YD	940	940														
21400100	GRADING AND SHAPING DITCHES	FOOT	3,440	3,440														
28100207	STONE RIPRAP, CLASS A4	TON	2060	2060														
28100805	STONE DUMPED RIPRAP, CLASS A3	TON	56	25					31									
28200200	FILTER FABRIC	SQ YD	1812	1812														
35300600	PORTLAND CEMENT CONCRETE BASE COURSE, 11"	SQ YD	158	158														
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	1,641	1,641														
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	300	300														
40600285	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	POUND	412,938	412,938														
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,836	2,836														
40600990	TEMPORARY RAMP	SQ YD	1,422	1,422														
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	52,941	52,941														
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	165				165											
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	65	65														

14

Rev. 11-5-14

	USER NAME : OPERATORS FILE NAME : WHKS.sht.500.dgn PLOT SCALE : 18.0000 / in. PLOT DATE : Aug-28-2014 9:11:42PM	DESIGNED - CHECKED - DRAWN - CHECKED -	REVISED REVISED REVISED REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES SCALE: SHEET NO. 1 OF 9 SHEETS STA. TO STA.	P.A.L. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO. T2 163 3 04-9-28.1RS-2&MISC STRUC REP CONTRACT NO. 72954 ILLINOIS FED. AID PROJECT
---	--	---	--	---	--	---