

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				FEDERAL FUNDS								
				90% FED / 10% STATE								
				6-00166-0000	6-00166-0000	6-00313-0000	6-00166-0000	6-00166-0000	6-00166-0000	6-00166-0000	6-00313-0000	
6-00313-0000												
				ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE
				0004	0014	0014	0014	0014	0014	0014	0014	0014
				IL 72	084-0126	084-0142	084-0136	084-0185	084-0127	084-0148	084-0148	084-0140,0141,0143
							084-0137		084-0128	084-0149		0144,0145,0146
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3,520	1,790					1,730			
50800515	BAR SPLICERS	EACH	26						26			
51100100	SLOPE WALL 4 INCH	SQ YD	469		447	22						
52000110	PREFORMED JOINT STRIP SEAL	FOOT	88.7						88.7			
54213447	END SECTIONS 12"	EACH	2	2								
X5810100	WATERPROOFING MEMBRANE SYSTEM (SPECIAL)	SQ YD	1,309.5			1,309.5						
59300100	CONTROLLED LOW STRENGTH MATERIAL	CU YD	2						2			
60100945	PIPE DRAINS, 12"	FOOT	20	20								
* 63000001	STEEL PLATE BEAM GUARDRAIL, TY A, 6' POSTS	FOOT	675	675								
* 63100085	TRAFFIC BARRIER TERMINAL, TY 6	EACH	4	4								
* 63100167	TRAFFIC BARRIER TERMINAL, TY 1 (SPECIAL) TANGENT	EACH	4	4								
63200310	GUARDRAIL REMOVAL	FOOT	1,767	1,767								
* 63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	75	75								
* 63301990	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINALS, TYPE 1	EACH	2	2								

* SPECIALTY ITEM

design firm
no. 184001036



USER NAME • gjonson	DESIGNED -	REVISED
FILE NAME • D872B54.sht_500.dgn	CHECKED -	REVISED
PLOT SCALE • 10.0000' / IN	DRAWN -	REVISED
PLOT DATE • 8/25/2014	CHECKED -	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 4 OF 9 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	-	SANGAMON	163	6
184-9-28JRS-2&MISC STRUC REP			CONTRACT NO. 72B54	
ILLINOIS FED. AID PROJECT				