

CONSTRUCTION CODE

FEDERAL FUNDS

90% FED / 10% STATE

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	6-00166-0000	6-00166-0000	6-00313-0000	6-00166-0000	6-00166-0000	6-00166-0000	6-00166-0000	6-00313-0000	
				6-00313-0000								
				ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE	
				0004	0014	0014	0014	0014	0014	0014	0014	
	IL 72	084-0126	084-0142	084-0136	084-0185	084-0127	084-0148	084-0140,0141,0143	084-0149	0144,0145,0146		
<input type="checkbox"/> X2503000	MAINTENANCE MOWING	ACRE	440	440								
<input type="checkbox"/> X0320157	CLEANING UNDERDRAIN OUTLETS	EACH	495	495								
X0322279	OUTLET MARKER	EACH	495	495								
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	10,909	10,909								
X0556100	PARTIAL DEPTH PATCHING (SPECIAL)	SQ YD	1,000	1,000								
X6061902	CONCRETE MEDIAN, TYPE SM (SPECIAL)	SQ FT	958	958								
X6090320	TYPE D INLET BOX, STANDARD 609006 (SPECIAL)	EACH	2	2								
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1								
X7010410	SPEED DISPLAY TRAILER	CAL MO	24	24								
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1								
* X7830072	GROOVING FOR RECESSED PAVEMENT MARKING 6"	FOOT	321,870	321,870								
Z0001495	BRIDGE APPROACH SHOULDER REMOVAL	SQ YD	55	55								
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	48				48					
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	1,309.5			1,309.5						

NON-PART. (100% STATE) * SPECIALTY ITEM

design firm
no. 184001038



USER NAME * g.jameson	DESIGNED -	REVISED
FILE NAME * 0672054_sht_500.dgn	CHECKED -	REVISED
PLOT SCALE * 10.0000 / IN	DRAWN -	REVISED
PLOT DATE * 8/25/2014	CHECKED -	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 8 OF 9 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	SANGAMON	163	10
*184-9-2&3IRS-2&MISC STRUE REP			CONTRACT NO. 72B54	
[ILLINOIS] FED. AID PROJECT				