


HMA REMOVAL SCHEDULE												
LOCATION	STATION	TO	STATION	LENGTH (FT)	HMA SURF REM, 3/4" (SQ YD)	HMA SURF REM, 1 1/2" (SQ YD)	HMA SURF REM, 2" (SQ YD)	HMA SURF REM, 2 1/2" (SQ YD)	HMA SURF REM, 3 1/4" (SQ YD)	HMA SURF REM, VAR. DEPTH (SQ YD)	PAVED SHLDR REM (SQ YD)	
CH 10 (WAVERLY RD.) RAMP A												
RAMP PVT	100+00.00	TO	105+86.70	587					587			
	105+86.70	TO	119+85.40	1,399				2,487				
	119+85.40	TO	120+85.00	100				456				
RT SHLD	100+00.00	RT	105+86.70	587		391						
	105+86.70	RT	119+85.40	1,399	932							
	119+85.40	RT	120+85.00	155	103							
LT SHLD	103+03.00	LT	105+86.70	284		267						
	105+86.70	LT	119+85.40	1,399	622							
	119+85.40	LT	120+85.00	103	46							
CH 10 (WAVERLY RD.) RAMP B												
RAMP PVT	200+23.00	TO	201+05.50	83				361				
	201+05.50	TO	213+63.10	1,258				2,236				
	213+63.10	TO	225+20.88	1,158				1,158				
RT SHLD	200+23.00	RT	201+05.50	129	86							
	201+05.50	RT	213+63.10	1,258	838							
	213+63.10	RT	225+20.88	1,158		772						
LT SHLD	200+23.00	LT	201+05.50	89	40							
	201+05.50	LT	213+63.10	1,258	559							
	213+63.10	LT	217+71.00	408		296						
CH 10 (WAVERLY RD.) RAMP C												
RAMP PVT	300+00.00	TO	305+86.70	587					587			
	305+86.70	TO	319+85.00	1,398				2,486				
	319+85.00	TO	320+85.00	100				457				
RT SHLD	300+00.00	RT	305+86.70	587		391						
	305+86.70	RT	319+85.00	1,398	932							
	319+85.00	RT	320+85.00	155	103							
LT SHLD	303+03.00	LT	305+86.70	284		268						
	305+86.70	LT	319+85.00	1,398	621							
	319+85.00	LT	320+85.00	103	46							
CH 10 (WAVERLY RD.) RAMP D												
RAMP PVT	400+23.00	TO	401+06.00	83				364				
	401+06.00	TO	413+63.10	1,257				2,235				
	413+63.10	TO	425+20.88	1,158				1,158				
RT SHLD	400+23.00	RT	401+06.00	129	86							
	401+06.00	RT	413+63.10	1,257	838							
	413+63.10	RT	425+20.88	1,158		772						
LT SHLD	400+23.00	LT	401+06.00	89	40							
	401+06.00	LT	413+63.10	1,257	559							
	413+63.10	LT	417+71.00	408		296						
IL RTE 54 (WABASH AVE.) RAMP A												
RAMP PVT	100+00.00	TO	105+85.00	585					585			
	105+85.00	TO	113+36.88	752				1,337				
RT SHLD	100+00.00	RT	105+85.00	585		390						
	105+85.00	RT	113+36.88	752	501							
LT SHLD	103+03.00	LT	105+85.00	282		267						
	105+85.00	LT	113+36.88	752	334							

HMA REMOVAL SCHEDULE												
LOCATION	STATION	TO	STATION	LENGTH (FT)	HMA SURF REM, 3/4" (SQ YD)	HMA SURF REM, 1 1/2" (SQ YD)	HMA SURF REM, 2" (SQ YD)	HMA SURF REM, 2 1/2" (SQ YD)	HMA SURF REM, 3 1/4" (SQ YD)	HMA SURF REM, VAR. DEPTH (SQ YD)	PAVED SHLDR REM (SQ YD)	
IL RTE 54 (WABASH AVE.) RAMP B												
RAMP PVT	221+56.84	TO	237+19.30	1,562						2,778		
	237+19.30	TO	248+77.33	1,158						1,158		
RT SHLD	221+46.84	RT	237+19.30	1,572	1,048							
	237+19.30	RT	248+77.33	1,158		772						
LT SHLD	221+46.84	LT	237+19.30	1,572	699							
	237+19.30	LT	241+24.64	405		294						
IL RTE 54 (WABASH AVE.) RAMP C												
RAMP PVT	300+00.00	TO	305+86.70	587						587		
	305+86.70	TO	311+11.46	525				933				
RT SHLD	300+00.00	RT	305+86.70	587		391						
	305+86.70	RT	311+11.46	525	350							
LT SHLD	303+03.00	LT	305+86.70	284		272						
	305+86.70	LT	311+11.46	525	233							
IL RTE 54 (WABASH AVE.) RAMP D												
RAMP PVT	418+27.27	TO	433+74.90	1,548						2,751		
	433+74.90	TO	445+33.53	1,159						1,159		
RT SHLD	418+27.27	RT	433+74.90	1,548	1,032							
	433+74.90	RT	445+33.53	1,159		772						
LT SHLD	418+27.27	LT	433+74.90	1,548	688							
	433+74.90	LT	437+79.91	405		292						
IL RTE 4 (VETERANS PKWY.) RAMP A												
RAMP PVT	100+00.00	TO	106+61.10	661						661		
	106+61.10	TO	115+26.91	866				1,539				
	115+26.91	TO	118+27.00	300				533				
	118+27.00	TO	121+13.00	286				636				
	121+13.00	TO	125+37.00	424				1,413				
	125+37.00	TO	126+53.00	116				464				
	126+53.00	TO	127+62.63	110				843				
RT SHLD	100+00.00	RT	106+61.10	661		441						
	106+61.10	RT	126+53.00	1,992				1,328				
	126+53.00	RT	127+62.63	234				156				
LT SHLD	103+00.00	LT	106+61.10	361		446						
	106+61.10	LT	115+28.00	867				385				
	115+28.00	LT	125+00.00	972				1,058				
	125+00.00	LT	125+35.00	35				27				
	125+35.00	LT	127+62.63	230				102				
IL RTE 4 (VETERANS PKWY.) RAMP B												
RAMP PVT	200+70.40	TO	201+84.00	114						321		
	201+84.00	TO	215+00.00	1,316						2,340		
	215+00.00	TO	226+22.87	1,123						1,123		
RT SHLD	200+70.40	RT	201+84.00	149	99							
	201+84.00	RT	215+00.00	1,316	877							
	215+00.00	RT	226+22.87	1,123		749						
LT SHLD	200+70.40	LT	201+84.00	114	50							
	201+84.00	LT	215+00.00	1,316	585							
	215+00.00	LT	218+52.00	352		319						



USER NAME = gjameson	DESIGNED -	REVISED
FILE NAME = D672854_sht_schedules.dwg	CHECKED -	REVISED
PLOT SCALE = 2.0000' / IN.	DRAWN -	REVISED
PLOT DATE = 8/25/2014	CHECKED -	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 2 OF 15 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72		SANGAMON	163	13
* (84-9-2&3)RS-2&MISC STRUC REP			CONTRACT NO. 72B54	
ILLINOIS FED. AID PROJECT				