


PAVING SCHEDULE

LOCATION	STATION	TO	STATION	LENGTH (FT)	BIT MATLS (PRIME COAT) (POUND)	POLY BIT MATLS (PRIME COAT) (POUND)	POLY HMA BIND CSE, IL- 19.0, N90 (TON)	POLY HMA SURF CSE, MIX "D", N90 (TON)	POLY HMA SURF CSE, MIX "E", N90 (TON)	HMA SURF CSE, MIX "D", N70 (TON)	HMA SHLDRS (TON)	SHLDR RUMB STRIPS, 16 INCH (FT)	AGGR. WEDGE SHLDR, TY B (TON)	HMA BSE CSE, 10" (SQ YD)	HMA SHLDRS 8" (SQ YD)	HMA SHLDRS 11 1/4" (SQ YD)	HMA SURF REM - BUTT JOINT (SY)	TEMP RAMP (SY)
IL RTE 4 (VETERANS PKWY.) RAMP D																		
RAMP PVT	400+56.20	TO	401+59.40	103		249	46		31								232	116
	401+59.40	TO	418+07.20	1,648		1,977	375		248									
	418+07.20	TO	426+33.80	827		558	110		73									
OUT SHLD	400+56.20	RT TO	410+59.40	RT 151		45					11		7					
	401+59.40	RT TO	426+33.80	RT 2,474		742					187		113					
INSIDE SHLD	400+56.20	LT TO	401+59.40	LT 103		21					5		5					
	401+59.40	LT TO	414+68.70	LT 1,309		262					66		60					
	414+68.70	LT TO	418+07.20	LT 339		106					28							
IL RTE 4 (VETERANS PKWY.) RAMP E																		
RAMP PVT	506+84.00	TO	523+09.40	1,625		1,950			326									
	523+09.40	TO	528+18.67	509		611	116		102									
	528+18.67	TO	534+32.17	614		368	61		62									
OUT SHLD	506+84.00	RT TO	534+32.17	RT 2,748		824					208		125					
INSIDE SHLD	506+84.00	LT TO	510+00.00	LT 316		63					16		14					
	510+00.00	LT TO	519+00.00	LT 900		441					111							
	519+00.00	LT TO	523+09.40	LT 409		82					21		19					
	523+09.40	LT TO	528+18.67	LT 509		138					26							
CHATHAM RD.																		
	156+94.40	RT TO	158+58.30	RT 164											146			
	156+35.70	LT TO	158+59.30	LT 224											199			
	157+96.20	TO	158+31.20	35	70				15								156	78
	158+31.20	TO	158+55.80	25	50				11									
	158+55.80	TO	158+81.20	25	30				7									
	164+22.40	TO	164+47.80	25	30				7									
	164+47.80	TO	164+72.40	25	50				11									
	164+72.40	TO	165+07.40	35	70				15								156	78
	164+50.30	RT TO	165+98.30	RT 148											132			
	164+28.90	LT TO	166+50.90	LT 222											197			
TOTALS =					300	412,938	52,941	23,697	12,799	65	31,233	263,773	13,951	1,641	673	5,014	2,836	1,422



USER NAME = g.jameson	DESIGNED -	REVISED
FILE NAME = D672B54_sht_schedules.dwg	CHECKED -	REVISED
PLOT SCALE = 2.0000' / IN.	DRAWN -	REVISED
PLOT DATE = 8/25/2014	CHECKED -	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO. 10 OF 15 SHEETS	STA.	TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72		SANGAMON	163	21
•(84-9-2&3)RS-2&MISC STRUC REP			CONTRACT NO. 72B54	
ILLINOIS FED. AID PROJECT				