


PAVEMENT MARKING SCHEDULE

LOCATION	STATION	TO	STATION	LENGTH	MODIFIED URETHANE PVT MKG- LINE 5"		GRV FOR RECESS PVT MKG 6"	PREF. PLASTIC PVT. MKG, TY. B -LINE 5"	PREF. PLASTIC PVT. MKG, TY. B INLAID-LINE 5"	MOD URETHANE PVT MKG - LINE 6"	MOD URETHANE PVT MKG - LINE 8"	MOD URETHANE PVT MKG - LINE 12"	PREF. PLASTIC PVT. MKG, TY. B INLAID-LINE 24"	PREF. PLASTIC PVT. MKG, TY. B INLAID-LET & SYMB	BARRIER WALL MKRS, TY C	RAISED REFL PVT MKRS	RAISED REFL PVT MKR REM	DELIN-EATORS	SHORT-TERM PVT MKG	WORK ZONE PVT. MKG REM.
					(FT)	WHITE (FT)														
I-72 EB MAINLINE																				
	10+00.00	TO	16+78.00	678	678	678	1,356		170							17	17		163	54
	16+78.00	TO	19+40.00	262	210	262	472		66							7	7		58	19
	19+40.00	TO	22+66.00	326		326	326		82	652	86					8	8		337	111
	22+66.00	TO	47+88.00	2,522	2,522	2,522	5,044		631							63	63		605	200
	47+88.00	TO	53+57.00	569		569	569		142	1,138						14	14		239	79
	53+57.00	TO	59+49.00	592		592	592		148							15	15		130	43
	59+49.00	TO	506+80.50	44,732	44,732	44,732	89,463		11,183							1,118	1,118		10,736	3,543
STA. EQ.	506+80.50 BK	=	1345+01.88 AH																	
	1345+01.88	TO	1348+78.00	376	376	376	752		94							9	9		90	30
	1348+78.00	TO	1351+39.00	261	209	261	470		65							7	7		57	19
	1351+39.00	TO	1354+65.00	326		326	326		82	652	86					8	8		337	111
	1354+65.00	TO	1368+35.00	1,370	1,370	1,370	2,740		343							34	34		329	109
	1368+35.00	TO	1370+65.00	230			518	518											55	18
	1370+65.00	TO	1378+37.00	772	772	772	1,544		193							19	19		185	61
	1378+37.00	TO	1379+01.88	65		65	65		16	130						2	2		227	75
STA. EQ.	1379+01.88 BK	=	379+01.88 AH																	
	379+01.88	TO	384+03.00	501		501	501		125	1,002						13	13		410	135
	384+03.00	TO	389+98.00	595		595	595		149							15	15		131	43
	389+98.00	TO	423+00.00	3,302	3,302	3,302	6,604		826							83	83		792	261
	423+00.00	TO	425+23.00	5,789	5,789	5,789	11,578		1,447							145	145		1,389	458
	425+23.00	TO	483+12.00	254	203	254	457		64							6	6		56	18
	483+12.00	TO	485+66.00	406		406	406		102	812	143					10	10		371	122
	485+66.00	TO	489+72.00	1,058	1,058	1,058	2,116		265							26	26		254	84
	489+72.00	TO	500+30.00	588		588	588		147	1,176						15	15		247	82
	500+30.00	TO	506+18.00	519		519	519		130							13	13		114	38
	506+18.00	TO	511+37.00	374	374	374	748		94							9	9		90	30
	511+37.00	TO	515+11.00	510		510	510		128	1,020						13	13		214	71
	515+11.00	TO	520+21.00	611		611	611		153							15	15		134	44
	520+21.00	TO	526+32.00	2,768	2,768	2,768	5,536		692							69	69		664	219
	526+32.00	TO	554+00.00																	
I-72 WB MAINLINE																				
	10+00.00	TO	12+71.00	271	271	271	542		68							7	7		65	21
	12+71.00	TO	18+63.00	592		592	592		148							15	15		130	43
	18+63.00	TO	24+33.00	570		570	570		143	1,140						14	14		239	79
	24+33.00	TO	49+55.00	2,522	2,522	2,522	5,044		631							63	63		605	200
	49+55.00	TO	52+80.00	325		325	325		81	650	86					8	8		337	111
	52+80.00	TO	55+42.00	262	210	262	472		66							7	7		58	19
	55+42.00	TO	506+80.50	45,139	45,139	45,139	90,277		11,285							1,128	1,128		10,833	3,575
STA. EQ.	506+80.50 BK	=	1345+01.88 AH																	
	1345+01.88	TO	1349+85.00	483	483	483	966		121							12	12		116	38
	1349+85.00	TO	1355+79.00	594		594	594		149							15	15		131	43
	1355+79.00	TO	1361+45.00	566		566	566		142	1,132						14	14		238	79
	1361+45.00	TO	1369+37.00	792	792	792	1,584		198							20	20		189	62
	1369+37.00	TO	1371+66.00	229			515	515											55	18
	1371+66.00	TO	1379+01.88	736	736	736	1,472		184							18	18		178	59



USER NAME = gjameson	DESIGNED -	REVISED
FILE NAME = D672B54_sht_schedules.dwg	CHECKED -	REVISED
PLOT SCALE = 2.0000' / IN.	DRAWN -	REVISED
PLOT DATE = 8/25/2014	CHECKED -	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 12 OF 15 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72		SANGAMON	163	23
* (84-9-2&3)RS-2&MISC STRUC REP			CONTRACT NO. 72B54	
ILLINOIS FED. AID PROJECT				