


CODE	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				F. A. P. 685 80% FEDERAL 20% STATE	F. A. P. 685 80% FEDERAL 20% STATE
				ROADWAY 0004	BOX CULVERT 0011
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1	
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	24	24	
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	248	248	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	105	105	
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	248	248	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2	2	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2	2	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0016702	DETOUR SIGNING	L SUM	1	1	
Z0023602	GRANULAR CULVERT BACKFILL	CU YD	684		684
* Z0054517	ROCK FILL - FOUNDATION	TON	493		493

* SPECIALTY ITEM

FILE NAME *	USER NAME * #USER*	DESIGNED -	REVISED -	 Allen Henderson & Associates, Inc. Civil and Structural Engineers Springfield, IL. 62703 Phone: (217)544-8033 IL Design Firm No. 184-001907	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	DRAWN -	REVISED -	685				(115)B-2	HANCOCK	28	5	
PLOT SCALE * #SCALE*	CHECKED -	REVISED -	SCALE:		SHEET NO. 3 OF 3 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			
PLOT DATE * #DATE*	DATE -	REVISED -	CONTRACT NO. 72F07								