

NOTES

Detail I - With Bar Splicer or Couplers:

Connect one (I) 1"x7"x10" steel £ to the top layer of couplers with 2-5g" \$\phi\$ boits screwed to coupler at approximate \$\mathbb{L}\$ of each barrier panel.

Detail II - With Extended Reinforcement Bars:

Connect one (1) 1"x7"x 10" steel £ to the concrete slab or concrete wearing surface with 2-5₈" \$

Expansion Anchors or cast in place inserts spaced between the top layer of reinforcement at approximate £ of each barrier panel.


Cost of anchorage is included with Temporary Concrete Barrier.


The 1" x 7" x 10" plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready to be placed.

SECTIONS THRU SLAB OR DECK BEAM

- *** Dimension shown is minimum required embedment into concrete.


 If hot-mix asphalt wearing surface is present, minimum embedment shall be in addition to wearing surface depth.
- **** If existing deck beam is to remain in place after stage construction, embedment shall only be into wearing surface and not into existing deck beam concrete.





** Wood blocks may be omitted when required to provide minimum stage traffic lane width. When the wood blocks are omitted, the concrete barrier shall be in direct contact with the steel retainer plate.

"W" = Top bars spacing + 4"



STEEL RETAINER P 1" x 7" x 10"

* Required only with Detail II

TEMPORARY CONCRETE BARRIER
FOR STAGE CONSTRUCTION
STRUCTURE NO. 051-2008

SHEET NO. 9	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	781	1098-1	LAWRENCE	34	23
	CONTRACT NO. 74105				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

ESCA
CONSULTANTS, INC.
DESIGNED BY: ELH 03/10
DRAWN BY: DWH 03/10
CHECKED BY: ELH 03/10
APPROVED BY: RDP 03/10

R-27

11-1-09