

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2012; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET, AND "THE SPECIAL PROVISIONS" INCLUDED IN THE PROPOSAL.

THE WORK INCLUDED IN THIS SECTION CONSISTS OF A COMPLETE DECK REPLACEMENT OF EXISTING STRUCTURES 018-0040 AND 018-0041, APPROACH PAVEMENTS AND PAVEMENT CONNECTORS, GUARDRAIL, AND ANY OTHER WORK NECESSARY TO COMPLETE THE PROJECT.

FIELD MARKINGS OF UNDERGROUND UTILITIES IN CRITICAL AREAS MAY BE OBTAINED BY PROVIDING A MINIMUM OF 96 HOURS ADVANCE NOTICE THROUGH THE J.U.L.I.E. SYSTEM BY CALLING 800-892-0123.

THE CONTRACTOR WILL PROVIDE INTERNET ACCESSIBILITY TO THE BITUMINOUS PLANT QUALITY CONTROL LAB SO THAT BITUMINOUS PLANT REPORTS CAN BE E-MAILED TO THE DISTRICT HEADQUARTERS. THE WORK SHALL BE INCLUDED IN THE COST OF ALL BITUMINOUS ITEMS.

TEMPORARY BARRIER WALL SHALL NOT BE PLACED ON THE PROJECT FROM THE MONTHS OF DECEMBER TO MARCH.

PIPE UNDERDRAINS FOR STRUCTURES SHALL EXTEND TO THE BOTTOM OF THE EMBANKMENT SLOPE AND TERMINATE WITH A PCC END SECTION.

THE QUANTITY OF WHITE 4" MODIFIED URETHANE PAVEMENT MARKING IS 348 FOOT, THE QUANTITY OF YELLOW 4" MODIFIED URETHANE PAVEMENT MARKING IS 348 FOOT, THE QUANTITY OF WHITE 6" MODIFIED URETHANE PAVEMENT MARKING IS 88 FOOT AND THE QUANTITY OF ONE WAY CRYSTAL REPLACEMENT REFLECTOR IS 100 EACH.

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE TO THIS PROJECT:

MIXTURE USE: HMA SHOULDERS, 2-1/2"
 APPLICATION: HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90
 PG GRADE: PG 64-22
 DESIGN AIR VOIDS: 4.0% @ NDESIGN = 90
 MIXTURE COMPOSITION: IL-9.5
 FRICTION AGGREGATE: MIXTURE C

MIXTURE USE: BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)
 APPLICATION: HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N70
 PG GRADE: PG 64-22
 DESIGN AIR VOIDS: 4.0% @ NDESIGN = 70
 MIXTURE COMPOSITION: IL-19.0
 FRICTION AGGREGATE: N/A

INDEX OF SHEETS

SHEET NO.	TITLE
1	COVER SHEET
2	INDEX OF SHEETS & GENERAL NOTES
3-4	SUMMARY OF QUANTITIES
5	SCHEDULES
6-7	STAGE CONSTRUCTION PLAN SHEETS
8-43	STRUCTURE PLAN SHEETS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 43:

000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND A FOOT
420401-10	BRIDGE APPROACH PAVEMENT CONNECTOR
515001-03	NAME PLATES
609006-05	BRIDGE APPROACH PAVEMENT (DRAIN DETAIL)
630001-10	STEEL PLATE BEAM GUARDRAIL
630301-06	SHOULDER WIDENING FOR TYPE1 (SPECIAL) GUARDRAIL TERMINALS
631031-12	TRAFFIC BARRIER TERMINAL, TYPE 6
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
642001-02	SHOULDER RUMBLE STRIPS, 16 IN
643001-02	SAND MODULE IMPACT ATTENUATORS
701101-04	OFF-ROAD OPERATIONS, MULTILANE 15' TO 24' FROM PAVEMENT EDGE
701400-07	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-08	LANE CLOSURE, FREEWAY/EXPRESSWAY
701402-09	LANE CLOSURE, FREEWAY/EXPRESSWAY, WITH BARRIER
701426-06	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS > = 45 MPH
701901-03	TRAFFIC CONTROL DEVICES
704001-07	TEMPORARY CONCRETE BARRIER
780001-04	TYPICAL PAVEMENT MARKINGS
781001-03	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS

FILE NAME :	USER NAME : steffennk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES & INDEX OF SHEETS					F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\steffennk\0254366\074187-ah-gegnote.dgn	DRAWN -	REVISED -	7D		118-45HB-118R	Cumberland	43	2						
PLOT SCALE = 1/8" = 1'-0"	CHECKED -	REVISED -	SCALE: SHEET OF SHEETS STA. TO STA.					CONTRACT NO. 74187						
Default	DATE -	REVISED -	ILLINOIS FED. AID PROJECT											