

PAVING SCHEDULES				44000151	44000155	40603243	40603545	40600275	48203100	48102100
STATION	TO	STATION	LENGTH (FT)	HMA SURF REM 1/2"	HMA SURF REM 1 1/2"	PLY HMA BINDER N90	PLY HMA SURF N90	BIT MT (PRM CT)	HMA SHLDRS	AGG WEDGE SHLDR TY B
			WIDTH (FT)	AREA (SQ YD)	(SQ YD)	(TON)	(TON)	(LB)	(TON)	(TON)

IL RT 37 SPUR				44000151	44000155	40603243	40603545	40600275	48203100	48102100	
STATION	TO	STATION	LENGTH (FT)	HMA SURF REM 1/2"	HMA SURF REM 1 1/2"	PLY HMA BINDER N90	PLY HMA SURF N90	BIT MT (PRM CT)	HMA SHLDRS	AGG WEDGE SHLDR TY B	
			WIDTH (FT)	AREA (SQ YD)	(SQ YD)	(TON)	(TON)	(LB)	(TON)	(TON)	
34+50.00		35+41.75	91.75	30	305.8	305.8		38.5	25.7	206.4	8.9
35+41.75		37+15.25	173.50	33	636.2	636.2		80.2	53.4	1817.4	56.1
37+15.25		38+12.50	97.25	30	324.2		324.2	27.2	257.7	14.5	6.3
38+12.50		48+82.00	1069.50	28	3327.3		3327.3	279.5	2673.8	159.7	69.5
48+82.00		51+35.40	BRIDGE OMISSION								
RAMP A											
51+35.40		56+24.40	489.00	14	760.7		760.7	63.9	440.1	36.5	
56+24.40 BK = 0+00.00 AH											
00+00.00		12+18.20	1218.20	14	1895.0	1895.0	238.8	159.2	2010.0	295.6	99.0
12+18.2 BK = 4662+84.50 AH											
4662+84.50		4668+14.10	529.60	8	470.8	470.8	59.3	39.5	635.5	128.5	43.0
4661+34.00		4665+28.80	394.80	5	219.3	219.3	27.6	18.4	384.9	95.8	32.1
RAMP B											
51+35.40		53+24.90	189.50	14	294.8		294.8	24.8	170.6	14.1	
53+24.90		56+24.90	300.00	15	500.0		500.0	42.0	285.0	22.4	
56+24.90 BK = 0+00.00 AH											
00+00.00		07+01.90	701.90	16	1247.8	1247.8		157.2	104.8	1263.4	170.3
7+01.90 BK = 4652+99.90 AH											
4652+99.90		4639+64.20	1335.70	11	1632.5	1632.5		205.7	137.1	1903.4	324.1
RAMP C											
36+72.10		42+46.50	574.4	14	893.5	893.5		112.6	75.1	947.8	139.4
42+46.50		43+97.60	151.1	3	50.4	50.4		6.3	4.2	124.7	36.7
42+46.50 BK = 0+00.00 AH											
00+00.00		13+13.70	1313.7	14	2043.5	2043.5		257.5	171.7	2167.6	318.8
13+13.70 BK = 4665+62 AH											
4655+62.00		4657+61.80	199.8	14	310.8	310.8		39.2	26.1	329.7	48.5
4657+61.80		4665+11.80	750.0	8	666.7	666.7		84.0	56.0	900.0	182.0
RAMP D											
4635+04.50		4640+33.50	529.00	14	822.9	822.9		103.7	69.1	872.9	128.4
4640+33.50		4641+84.60	151.10	4	67.2	67.2		8.5	5.6	136.0	36.7
4640+33.50 BK = 0+00 AH											
00+00.00		09+85.80	985.80	14	1533.5	1533.5		193.2	128.8	1626.6	239.2
9+85.80 BK = 41+48.60 AH											
41+48.60		36+76.10	472.5	11	577.5	577.5		72.8	48.5	673.3	114.7
TOTAL PAGE 1=				13373	5207	1685	1561	19827	2562	852	