PAVEMENT MARKING SCHEDULES				78000200 THERMO PVT MRK 4" WHITE (FOOT)	78000200 THERMO PVT MRK 4" YELLOW (FOOT)	X7830070 GRV FOR REC PVT MRK 5" (FOOT)	78000500 THERMO PVT MRK 8" WHITE (FOOT)	X7830076 GRV FOR REC PVT MRK 9" (FOOT)	78000600 THERMO PVT MRK 12" YELLOW (FOOT)	X7830078 GRV FOR REC PVT MRK 13" (FOOT)	70300100 SHRT TRM PVT MRK (FOOT)	70301000 WRK ZN PVT MRK REM (SQ FT)	70300220 TEMP PVT MRK 4" (FOOT)	70300250 TEMP PVT MRK 8" (FOOT)	70300260 TEMP PVT MRK 12" (FOOT)
STATION	TO	STATION	LENGTH (FT)												
IL RT 37 SPUR															
34+50.00		34+85.00	35.00	35.0	40.0	75.0					9.0	1.0	75.0		
34+85.00		35+40.80	55.80	111.6	69.8	181.4					21.8	2.4	181.4		
35+40.80		37+15.00	174.20	348.4	696.8	1045.2			35.0	35.0	125.4	13.9	1045.2		35.0
37+15.00		41+90.00	475.00		950.0	950.0					76.0	12.7	950.0		
41+90.00		48+82.00	692.00	1114.0	1384.0	2498.0	42.0	42.0			199.8	33.3	2498.0	42.0	
48+82.00		51+35.40	253.40	506.8	506.8	1013.6	224.0	224.0			81.1	13.5	1013.6	224.0	
RAMP A															
51+35.40		56+24.40	489.00	489.0	489.0	978.0					78.2	13.0	978.0		
56+24.40 BK = 0+00.00 AH															
00+00.00		11+62.00	1162.00	1162.0	1162.0	2324.0					278.9	31.0	2324.0		
11+62.00		12+18.20	56.20	56.2		56.2	56.2	56.2			6.7	0.7	56.2	56.2	
12+18.2 BK= 4662+84.50 AH															
4662+84.50		4665+28.80	244.30	244.3		244.3	244.3	244.3			29.3	3.3	244.3	244.3	
4665+28.80		4668+14.10	285.30	285.3		285.3					34.2	3.8	285.3		
RAMP B															
51+35.40		56+24.90	489.50	489.5	489.5	979.0					78.3	13.1	979.0		
56+24.90 BK = 0+00.00 AH															
00+00.00		05+67.00	567.00	567.0	567.0	1134.0					136.1	15.1	1134.0		
05+67.00		06+35.00	68.00	68.0	68.0	136.0	68.0	68.0			16.3	1.8	136.0	68.0	
06+35.00		07+01.90	66.90	66.9		66.9					8.0	0.9	66.9		
7+01.90 BK = 4652+99.90 AH															
4652+99.90		4650+42.00	257.90	257.9		257.9					30.9	3.4	257.9		
4650+42.00		4638+64.20	1177.80	1177.8		1177.8					141.3	15.7	1177.8		
RAMP C															
37+15.00		42+46.50	531.5	531.5		531.5	135.0	135.0			63.8	7.1	531.5	135.0	
42+46.50 BK = 0+00.00 AH															
00+00.00		11+00.00	1100.0	1100.0	1100.0	2200.0					264.0	29.3	2200.0		
11+00.00		12+40.00	140.0	140.0		140.0					16.8	1.9	140.0		
12+40.00		13+13.70	73.7	73.7		73.7	73.7	73.7			8.8	1.0	73.7	73.7	
13+13.70 BK = 4665+62 AH															
4655+62.00		4657+61.80	199.8	199.8		199.8					24.0	2.7	199.8		
4657+61.80		4665+11.80	750.0	750.0		750.0					90.0	10.0	750.0		
RAMP D															
4635+04.60		4637+90.10	285.50	285.5		285.5					34.3	3.8	285.5		
4637+90.10		4640+33.50	243.40	243.4		243.4	243.4	243.4			29.2	3.2	243.4	243.4	
4640+33.50 BK = 0+00 AH															
00+00.00		00+72.00	72.00	72.0		72.0	72.0	72.0			8.6	1.0	72.0	72.0	
00+72.00		09+85.80	913.80	913.8	913.8	1827.6					219.3	24.4	1827.6		
9+85.80 BK = 41+48.60 AH															
41+48.60		36+76.10	472.5	472.5		472.5	120.0	120.0			56.7	6.3	472.5	120.0	
			TOTAL=	11762	8437	20199	1279	1279	35	35	2167	269	20199	1279	35