

GUARDRAIL SCHEDULES					STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	STEEL RAILING, TYPE 2399	TRAFFIC BARRIER TERMINAL, TYPE 6A	TRAFFIC BARRIER TERMINAL, TYPE 6B	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL, TYPE 2	GUARDRAIL REMOVAL	GUARDRAIL MARKER, TYPE A	TERMINAL MARKER - DIRECT APPLIED
NORTHBOUND I-57					FT	FT	EACH	EACH	EACH	EACH	FT	EACH	EACH
RT STA	4621+93	TO	RT STA	4625+62	287.5		1		1		369	4	1
LT STA	4623+31	TO	LT STA	4630+07	137.5		1		1		676	4	1
RT STA	4643+56	TO	RT STA	4646+85	237.5			1	1		329.0	4	1
RT STA	4723+95	TO	RT STA	4727+12	225			1	1		317.0	4	1
RT STA	4777+13	TO	RT STA	4780+29	225			1	1		316.0	4	1
RT STA	4886+62	TO	RT STA	4889+79	225			1	1		317.0	4	1
LT STA	4943+15	TO	LT STA	4946+83	312.5				1	1	368.0	4	1
RT STA	4943+77	TO	RT STA	4946+94	262.5				1	1	317.0	4	1
RT STA	4963+66	TO	RT STA	4969+31	512.5				1	1	565.0	7	1
LT STA	4970+48	TO	LT STA	4978+49	750				1	1	801.0	10	1
RT STA	4971+14	TO	RT STA	4978+62	687.5				1	1	748.0	9	1
LT STA	5013+49	TO	LT STA	5022+60	850				1	1	911.0	11	1
RT STA	5016+82	TO	RT STA	5023+10	575				1	1	628.0	8	1

SOUTHBOUND I-57					FT	FT	EACH	EACH	EACH	EACH	FT	EACH	EACH
RT STA	4625+59	TO	RT STA	4632+72	175		1		1		713.0	4	1
LT STA	4625+59	TO	LT STA	4632+72	175		1		1		609.0	4	1
RT STA	4646+93	TO	RT STA	4650+22	237.5			1	1		329.0	4	1
LT STA	4646+49	TO	LT STA	4650+63	362.5				1	1	414.0	5	1
RT STA	4726+47	TO	RT STA	4729+64	225			1	1		317.0	4	1
RT STA	4780+10	TO	RT STA	4783+26	225			1	1		316.0	4	1
RT STA	4889+40	TO	RT STA	4892+57	225			1	1		317.0	4	1
RT STA	4947+33	TO	RT STA	4950+87	300				1	1	354.0	4	1
RT STA	5000+09	TO	RT STA	5002+98	237.5				1	1	289.0	4	1
LT STA	5000+25	TO	LT STA	5003+53	275				1	1	328.0	4	1
TOTAL PAGE 1=					7725	0	4	8	23	11	10648	119	23

GUARDRAIL SCHEDULES CONTINUED					STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	STEEL RAILING, TYPE 2399	TRAFFIC BARRIER TERMINAL, TYPE 6A	TRAFFIC BARRIER TERMINAL, TYPE 6B	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL, TYPE 2	GUARDRAIL REMOVAL	GUARDRAIL MARKER, TYPE A	TERMINAL MARKER - DIRECT APPLIED	
IL 37					FT	FT	EACH	EACH	EACH	EACH	FT	EACH	EACH	
RT STA	39+75.00	TO	RT STA	41+13.00	82.5				1	1	138.0	4	1	
RT STA	46+83.00	TO	RT STA	48+85.00	112.5			1		1		202.0	4	1
LT STA	51+27.00	TO	LT STA	53+21.00	112.5			1		1		194.0	4	1
SN 025-0061, 700th AVENUE														
NORTHEAST CORNER					100	221	1		1		117.0	5	1	
SOUTHEAST CORNER					100	221	1		1			5	1	
SOUTHWEST CORNER					100		1		1		117.0	3	1	
NORTHWEST CORNER					100		1		1			3	1	
SN 025-0053, 800th AVENUE														
NORTHEAST CORNER					100		1		1		90.0	5	1	
SOUTHEAST CORNER					100		1		1		65.0	5	1	
SOUTHWEST CORNER					100		1		1		90.0	3	1	
NORTHWEST CORNER					100		1		1		65.0	3	1	
SN 025-0060, 1000th AVENUE														
NORTHEAST CORNER					100	220	1		1		117.0	5	1	
SOUTHEAST CORNER					100	220	1		1			5	1	
SOUTHWEST CORNER					100		1		1		117.0	3	1	
NORTHWEST CORNER					100		1		1			3	1	
TOTAL PAGE 2=					1507.5	882	14	0	15	1	1312	60	15	

TOTAL PAGE 1=	7725	0	4	8	23	11	10648	119	23
TOTAL PAGE 2=	1507.5	882	14	0	15	1	1312	60	15
TOTAL GUARDRAIL QUANTITIES=	9232.5	882	18	8	38	12	11960	179	38

70400100 TEMPORARY CONCRETE BARRIER

		STATION	STATION	FOOT
STAGE 1	NORTHBOUND	4623+69	4630+13	644.0
STAGE 1	SOUTHBOUND	4625+53	4632+03	650.0
TOTAL=				1294.0

70400200 RELOCATE CONCRETE BARRIER

		STATION	STATION	FOOT
STAGE 1	NORTHBOUND	4623+69	4630+13	644.0
STAGE 1	SOUTHBOUND	4625+53	4632+03	650.0
TOTAL=				1294.0

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
c:\pwwork\pwwork\stefjenmk\d0401616\07	4638-sh-t-schedules.dgn	DRAWN -	REVISED -
Default	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 9/8/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N/A SHEET 5 OF 5 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(25-6,7)RS-2	EFFINGHAM	63	14
CONTRACT NO. 74638			ILLINOIS FED. AID PROJECT	