



**HALF PLAN**

Showing West Parapet, East Parapet similar by rotation.

**NOTES:**

New Railing to be installed on west parapet of the North Bound Lanes SN 025-0071 and each parapet of South Bound Lanes SN 025-0072.

Existing Tri-Beam Rail to be removed and replaced, existing anchor bolts to be cut off flush with concrete and ground smooth.

DESIGNED SMR	EXAMINED <i>Timothy A. [Signature]</i>	DATE October 15, 2014
CHECKED CCC	ACTING ENGINEER OF STRUCTURAL SERVICES	
DRAWN J. Schneller	PASSED <i>[Signature]</i>	REVISED
CHECKED SMR CCC	ACTING ENGINEER OF BRIDGES AND STRUCTURES	REVISED

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**STEEL BRIDGE RAIL (2399) DETAILS  
SN 025-0071 & 025-0072**

SHEET NO. 20 OF 22 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(25-6, 7)RS-2	EFFINGHAM	63	48
CONTRACT NO. 74638			ILLINOIS FED. AID PROJECT	