

100% STATE

100% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		COLES COUNTY 0014	CUMBERLAND COUNTY 0014
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	3546	1897	1649
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1001	590	411
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	2	2
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.5	0.5
70300100	SHORT TERM PAVEMENT MARKING	FOOT	328	167	161
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	50 FT	108	55	53
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3636	1852	1784
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	455	232	223
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	45	23	22
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	50 YD	7880	4215	3665
X7010410	SPEED DISPLAY TRAILER	CAL MO	3	1.5	1.5

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		COLES COUNTY 0014	CUMBERLAND COUNTY 0014
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28	14	14
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	3636	1852	1784
* X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	455	232	223
Z0005010	HOT-MIX ASPHALT FOR PATCHING POTHOLES (COLD MIX)	TON	2	1	1
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	250	125	125

\* SPECIALTY ITEM

\* COLES, CUMBERLAND

FILE NAME =	USER NAME = atoffennk	DESIGNED -	REVISD -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\p\work\p\dot\atoffennk\08396917107	74677-ahs-aag.dgn	DRAWN -	REVISD -			57	07 BRIDGE REPAIRS 2015-1		8	3	
Default	PLOT SCALE = 100.0000 1/ in.	CHECKED -	REVISD -			SCALE: N/A SHEET 1 OF 1 SHEETS STA. TO STA.		CONTRACT NO. 74677			
	PLOT DATE = 8/4/2014	DATE -	REVISD -			ILLINOIS FED. AID PROJECT					