

INDEX OF SHEETS

SHEET NO.	ITEM
1	COVER SHEET
2	INDEX OF SHEETS, GENERAL NOTES & LOCATION DESCRIPTIONS
3	SUMMARY OF QUANTITIES
4-9	EXISTING STRUCTURE PLANS
10	LOCATION MAPS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 10:

STD. NO.	DESCRIPTION
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
701001-02	OFF-ROAD OPERATIONS, 2L2W, 15' MINIMUM AWAY FROM PAVEMENT EDGE
701006-05	OFF-ROAD OPERATIONS, 2L2W, 15' AWAY TO EDGE OF PAVEMENT
701201-04	LANE CLOSURE, 2L2W, DAY ONLY
701901-03	TRAFFIC CONTROL DEVICES

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2012; THE SUPPLEMENTAL SPECIFICATIONS, THE RECURRING SPECIAL PROVISIONS, AND THE SPECIAL PROVISIONS INCLUDED IN THE PROPOSAL.

THE PROPOSED PROJECT IS LOCATED AT TWO LOCATIONS ON ILLINOIS ROUTES 121 AND 128 IN MOULTRIE AND SHELBY COUNTIES.

THE WORK INCLUDED IN THIS SECTION CONSISTS OF CLEANING AND PAINTING BRIDGES AT TWO LOCATIONS AS SPECIFIED ELSEWHERE IN THESE PLANS AND THE SPECIAL PROVISIONS.

THE STRUCTURAL STEEL SHALL BE CLEANED AND PAINTED AS SPECIFIED IN THE SPECIAL PROVISIONS.

ALL DECK DRAINS SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1 - OZ/E/U. ANY DAMAGE CAUSED BY THE CONTRACTOR SHALL BE REPAIRED AT THEIR OWN EXPENSE AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

ALL TRASH AND PAINTING DEBRIS, EXCLUDING WASTE BARRELS OR ROLL - OFF DUMPSTERS, SHALL BE REMOVED BEFORE BEGINNING WORK AT ANOTHER LOCATION.

ONLY STRUCTURAL STEEL IS TO BE PAINTED. ALL OTHER SURFACES WILL BE PROTECTED FROM BEING PAINTED. ALL PAINT AND OVERSPRAY WILL BE REMOVED AT THE CONTRACTOR'S EXPENSE.

THE SSPC OP1 AND OP2 PAINTING CONTRACTOR CERTIFICATION WILL BE REQUIRED FOR THIS PROJECT.

BRIDGE LOCATION DESCRIPTIONS

LOCATION #1

ROUTE: FAP 320
 MARKED: ILL 121
 SECTION: 103BR
 STATION: 399+37.25
 STRUCTURE NUMBER: 070-0002

TYPE OF BRIDGE: Wide Flange I Beams-6 Spans (6 Beams)
 LOCATION: Southeast of Bethony
 FEATURE CARRIED/SPANNED: ILL 121 over the West Okaw River

COLOR OF THE FINISH COAT SHALL BE GRAY, MUNSELL 5B 7/1.

Cleaning and painting of the existing structural steel shall be as specified in the special provision for "Cleaning and Painting Existing Steel Structures". All structural steel within 5' (measured along the beam) of the abutments and any expansion joints at piers, including beams, bearings and diaphragms, shall be cleaned by SSPC-SP10- Near White Metal Blast Cleaning. Both fascia beams shall be painted in their entirety, for the entire length of the beams, and they shall be cleaned by SSPC-SP10- Near White Metal Blast Cleaning.

The designated areas cleaned per Near White Metal Blast Cleaning - SSPC-SP10 shall be painted according to the requirements of Paint System 1 - OZ/E/U.

One air monitor will be required at this location.

LOCATION #2

ROUTE: FAP 774
 MARKED: ILL 128
 SECTION: 101VB-1
 STATION: 21+52.97
 STRUCTURE NUMBERS: 087-0021

TYPE OF BRIDGES: Wide Flange I Beams-3 Spans (6 Beams)
 LOCATION: 0.5 miles south of Illinois Route 16
 FEATURE CARRIED/SPANNED: ILL 128 over CNRL RR (Abandoned)

COLOR OF THE FINISH COAT SHALL BE GREEN, MUNSELL 10B 3/6 FOR ALL BEAMS.

Cleaning and painting of the existing structural steel shall be as specified in the special provision for "Cleaning and Painting Existing Steel Structures". All structural steel within 5' (measured along the beam) of the abutments, including beams, bearings and diaphragms, shall be cleaned by SSPC-SP10- Near White Metal Blast Cleaning. The entire outside and bottom of the bottom flange of both fascia beams, for the entire length of the beams, shall be cleaned by SSPC-SP10- Near White Metal Blast Cleaning.

The designated areas cleaned per Near White Metal Blast Cleaning - SSPC-SP10 shall be painted according to the requirements of Paint System 1 - OZ/E/U.

One air monitor will be required at this location.

FILE NAME :	USER NAME : astaffennk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES AND BRIDGE LOCATION DESCRIPTIONS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pudot\astaffennk\d039705610	74683-ent-index.dgn	DRAWN -	REVISED -			774	D7 BRIDGE PAINTING 2015-1	*	10	2	
Default	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -			CONTRACT NO. 74683					
	PLOT DATE = 8/4/2014	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					

* MOULTRIE & SHELBY

SCALE: N/A SHEET 1 OF 1 SHEETS STA. TO STA.