

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				80/20 FED / STATE ROADWAY 0004 RURAL
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3	3
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4	4
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	4	4
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	4	4
54260311	TRAVERSABLE PIPE GRATE	FOOT	115	115
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	15	15
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	111	111
59000200	EPOXY CRACK INJECTION	FOOT	48	48
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	7.1	7.1
60221100	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1
60224448	MANHOLES, TYPE A, 7' -DIAMETER, TYPE 8 GRATE	EACH	1	1
60500060	REMOVING INLETS	EACH	1	1
60600095	CLASS S1 CONCRETE (OUTLET)	CU YD	9	9
60602800	CONCRETE GUTTER, TYPE B	FOOT	675	675

• FAS 752/FAS 749

FILE NAME =	USER NAME = herbaughhd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ar\pr_work\psidat\herbaughhd\0130105\076709-ant-500.dgn	DRAWN -	REVISED -	REVISED -		•	101-2RS-1	JERSEY	438	11				
PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -	REVISED -		CONTRACT NO. 76789								
PLOT DATE = 8/22/2014	DATE -	REVISED -	REVISED -		SCALE: N/A	SHEET NO. 9 OF 14 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			