

GENERAL NOTES

1. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE TO BE GIVEN TO ALL UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

- AMEREN ILLINOIS (GAS & ELECTRIC)
- AT&T ILLINOIS (COMMUNICATIONS)
- CHARTER COMMUNICATIONS, INC. (CABLE TV)
- CLEARWAVE COMMUNICATIONS (COMMUNICATIONS)
- COUNTRYMARK COOPERATIVE, LLP (PIPELINE)
- FRONTIER NORTH, INC. (COMMUNICATIONS)
- HARRISONVILLE TELEPHONE COMPANY (COMMUNICATIONS)
- MASCOUTAH COMMUNITY UNIT SCHOOL DISTRICT #19 (COMMUNICATIONS)
- MEDIACOM (CABLE TV)
- MONROE COUNTY ELECTRIC CO-OPERATIVE, INC. (ELECTRIC)
- TRI-COUNTY ELECTRIC COOPERATIVE, INC. (ELECTRIC)
- WASHINGTON COUNTY WATER CO. (WATER)

MEMBERS OF J.U.L.I.E. CALL TOLL FREE (800)892-0123 OR 811 AND ARE INDICATED BY *. NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
3. ONLY SHORT TERM LANE CLOSURES SHALL BE ALLOWED FOR MOVEMENT OF EQUIPMENT AND AS DIRECTED BY THE ENGINEER.
4. FLAGGERS SHALL BE PRESENT DURING LANE CLOSURES AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.
5. THE CONTRACTOR SHALL BE AWARE OF THE CONDITIONS OF THE 404 PERMIT REGARDING EROSION CONTROL MEASURES AND BE IN COMPLIANCE WITH THEM.
6. IN ORDER TO AVOID EROSION OF THE EXCAVATED AREAS, THE CONTRACTOR SHALL HAVE RIPRAP PLACED WITHIN 24 HOURS OF EXCAVATION UNLESS OTHERWISE DIRECTED BY THE ENGINEER DUE TO ADVERSE WEATHER CONDITIONS.
7. "TRUCKS ENTERING AND LEAVING" SIGNS SHALL BE REQUIRED AND PLACED ACCORDING TO THE ENGINEER'S DISCRETION. NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
8. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING AND MAINTAINING ACCESS TO WORK AREAS. NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
9. ANY AREAS DISTURBED FOR ANY REASON SHALL BE TEMPORARILY AND PERMANENTLY SEEDED AS DIRECTED BY THE ENGINEER AT THE CONTRACTOR'S EXPENSE.
10. THE ILLINOIS DEPARTMENT OF TRANSPORTATION STRONGLY ENCOURAGES THE PRIME CONTRACTOR AND THEIR APPROVED SUB-CONTRACTORS TO HIRE MINORITY, WOMEN, AND DISADVANTAGED INDIVIDUALS FROM ITS FEDERALLY FUNDED HIGHWAY CONSTRUCTION CAREERS TRAINING PROGRAM (HCCTP) TO HELP MEET WORKFORCE AND TRAINEE GOALS. THIS PROGRAM IS TRAINING MINORITIES, WOMEN AND DISADVANTAGED INDIVIDUALS IN HIGHWAY CONSTRUCTION-RELATED SKILLS, E.G., MATH FOR THE TRADES, JOB READINESS, TECHNICAL SKILLS COURSEWORK (CARPENTRY, CONCRETE FLATWORK, BLUEPRINT READING, SITE PLANS, SITE WORK, TOOLS USE, ETC.) AND OSHA 10 HOUR CERTIFICATION, TO PREPARE THEM FOR A CAREER IN THE HIGHWAY CONSTRUCTION TRADES. GRADUATES ARE WELL-TRAINED AND READY TO BECOME PRODUCTIVE ENTRY-LEVEL CONSTRUCTION WORKERS. PLEASE CONTACT THE DISTRICT 8 EEO OFFICE AT 618-346-3360 AND/OR THE HCCTP COORDINATOR AT 618-874-6528 TO LEARN MORE ABOUT THE PROGRAM AND FOR ASSISTANCE IN MEETING WORKFORCE AND TRAINEE GOALS.

INDEX OF SHEETS

- 1 COVER SHEET
- 2 GENERAL NOTES, HIGHWAY STANDARDS, COMMITMENTS, ADT
- 3 SUMMARY OF QUANTITIES
- 4-6 LOCATION MAPS
- 7-10 PLAN SHEETS

HIGHWAY STANDARDS

- 000001-06
- 701001-02
- 701006-05
- 701201-04
- 701301-04
- 701901-03

COMMITMENTS

NONE

ADT

LOCATION 1
MONROE COUNTY
2013 ADT = 4250 (ACTUAL)
2014 ADT = 4300 (ESTIMATED)
SU = 5.1%
MU = 2.8%

LOCATION 2
ST. CLAIR COUNTY
2013 ADT = 2800 (ACTUAL)
2014 ADT = 2850 (ESTIMATED)
SU = 3.2%
MU = 3.2%

LOCATION 3
WASHINGTON COUNTY
2013 ADT = 2200 (ACTUAL)
2014 ADT = 2250 (ESTIMATED)
SU = 4.1%
MU = 2.7%

LOCATION 4
WASHINGTON COUNTY
2013 ADT = 2000 (ACTUAL)
2014 ADT = 2050 (ESTIMATED)
SU = 3.5%
MU = 3.0%

FILE NAME =	USER NAME = eonoverpj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES, INDEX OF SHEETS, ADT, HIGHWAY STANDARDS, COMMITMENTS	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
e:\p\work\p\idat\eonoverpj\d8403185108	SH43-akt-gennote.dgn	DRAWN -	REVISED -			VAR.	DIST 8 SCOUR MIT 2015-2	VARIOUS	10	2	
	PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISED -			CONTRACT NO. 76H43					
	PLOT DATE = 8/18/2014	DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.