

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE BOX CULVERT
				0004 RURAL	0011 S.N. 041-2021
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	204	204	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1	
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	133		133
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	36660		36660
50800515	BAR SPLICERS	EACH	223		223
50900200	STEEL RAILING, TYPE 2399	FOOT	82		82
51500100	NAME PLATES	EACH	1		1
54003000	CONCRETE BOX CULVERTS	CU YD	226.8		226.8
• 542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	50	50	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1	
• 54248510	CONCRETE COLLAR	CU YD	0.9	0.9	
△ 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	75	75	
△ 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	

- SEE SPECIAL PROVISIONS
- △ DENOTES SPECIALTY ITEM

FILE NAME = D:\78210-111-500.dgn
 MODEL = 04/24/14
 PLOT DRIVER = 1001.PDF.plt



QUIGG ENGINEERING INC

USER NAME = twalker	DESIGNED - MCV	REVISED -
FILE NAME = D:\78210-111-500.dgn	DRAWN - CMM	REVISED -
PLOT SCALE = 40.0000' / 1"	CHECKED - MTM	REVISED -
PLOT DATE = 5/29/2014	DATE - 4/25/2014	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 3 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
84B	113B-1	JEFFERSON	36	5
CONTRACT NO. 78210				
ILLINOIS FED. AID PROJECT				