

EARTHWORK SCHEDULE						
LOCATION			EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT (NOT A PAY ITEM)	BALANCE WASTE (+) OR SHORTAGE (-)
STA	TO	STA	CU YD	CU YD	CU YD	CU YD
45+50.00		47+80.00	230	173	520	-347
49+60.00		52+00.00	85	64	260	-196
TOTALS			315	237	780	-543

SEEDING SCHEDULE											
LOCATION				MULCH METHOD 2	SEEDING, CLASS 2A	SEEDING CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	HEAVY DUTY EROS CONT BLANKET
STA	TO	STA	OFF	ACRE	ACRE	ACRE	POUND	POUND	POUND	TON	SQ YD
45+53.00		47+83.54	LT	0.11	0.11	0.11	9	9	9	0.2	357
45+53.00		47+83.54	RT	0.30	0.30	0.30	32	32	32	0.6	1275
49+56.46		51+87.00	LT	0.22	0.22	0.22	23	23	23	0.4	912
49+56.46		51+87.00	RT	0.12	0.12	0.12	12	12	12	0.2	484
TOTALS				0.75	0.75	0.75	76	76	76	1.4	3028

NOTES:  
1. ASSUME 25% SHRINKAGE

EROSION CONTROL SCHEDULE						
LOCATION				TEMPORARY EROSION CONTROL SEEDING (2 APPS)	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER
STA	TO	STA	OFF	POUND	FOOT	FOOT
45+53.00		47+83.54		15		263
45+53.00		47+83.54		53		407
49+56.46		51+87.00		38		278
49+56.46		51+87.00		20		260
46+25.00		46+25.00	60.5' RT		14	
47+00.00		47+00.00	61.5' RT		17	
47+75.00		47+75.00	71.5' RT		12	
TOTALS				126	43	1208

REMOVAL SCHEDULE					
LOCATION				HMA SURF REM - BUTT JOINT	PAVEMENT REMOVAL
STA	TO	STA	OFF	SQ YD	SQ YD
45+53.00		45+83.00		89	
51+57.00		51+87.00		87	
47+40.00		47+80.00			115 •
49+60.00		50+00.00			118 •
TOTALS				176	233

• INCLUDES REMOVAL OF BRIDGE APPROACH

PAVING SCHEDULE							
LOCATION				LEVELING BINDER (MM, N90)	HMA SURFACE CSE, MIX "C", N90	BRIDGE APPR PVMT CONNECTOR (FLEXIBLE)	BITUMINOUS MATERIALS (PRIME COAT)
STA	TO	STA	OFF	TON	TON	SQ YD	POUND
46+03.00		47+40.00		18			99
50+00.00		51+37.00		18			99
45+53.00		47+40.00			46		257
50+00.00		51+87.00			46		257
47+40.00		47+50.00				38	65
49+90.00		50+00.00				38	65
TOTALS				36	92	76	842

PAVEMENT MARKING SCHEDULE					
LOCATION				DESCRIPTION	PAINT PAVEMENT MARKING - LINE 4"
STA	TO	STA	OFF		FOOT
45+53.00		51+87.00		SKIP-DASH	160
45+53.00		51+87.00		LT EDGE	634
45+53.00		51+87.00		RT EDGE	634
TOTALS					1428

RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE				
LOCATION		RAISED REFL PVMT MKR	RAISED REFL PVMT MKR (BRIDGE)	RAISED REFL PVMT MKR REMOVAL
STA	OFF	EACH	EACH	EACH
STA 45+86.00		1		1
STA 46+66.00		1		1
STA 47+46.00		1		1
STA 48+26.00			1	
STA 49+06.00			1	
STA 49+86.00			1	1
STA 50+66.00		1		1
STA 51+46.00		1		1
TOTALS		5	3	6

SHOULDER SCHEDULE				
LOCATION				HMA SHOULDERS, 8"
STA	TO	STA	OFF	SQ YD
45+53.00		45+98.00	RT	15
45+53.00		45+98.00	LT	15
51+42.00		51+87.00	RT	15
51+42.00		51+87.00	LT	15
45+98.00		47+65.00	RT	115
45+98.00		47+65.00	LT	94
49+60.00		51+42.00	RT	94
49+60.00		51+42.00	LT	115
TOTALS				478

GUARDRAIL SCHEDULE					
LOCATION	SPBGR, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL TYPE 6	TRAFFIC BARRIER TERMINAL TYPE 1 (SPL ) TAN	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER - DIRECT APPLIED
	FOOT	EACH	EACH	EACH	EACH
STRUCTURE NO. 097-0027 - SW	62.5	1	1	4	1
STRUCTURE NO. 097-0027 - SE		1	1	4	1
STRUCTURE NO. 097-0027 - NW		1	1	4	1
STRUCTURE NO. 097-0027 - NE	62.5	1	1	4	1
TOTALS	125	4	4	16	4

GUARDRAIL REMOVAL SCHEDULE	
LOCATION	FOOT
SN 097-0027 - (IL 141) RT	499
SN 097-0027 - (IL 141) LT	499
TOTALS	998

DRAINAGE SCHEDULE						
LOCATION		METAL END SECTIONS 12"	PIPE DRAINS 12"	TYPE B INLET BOX, STD 609006	CONCRETE THRUST BLOCKS	STONE RIPRAP, CLASS A3
STA	OFF	EACH	FOOT	EACH	EACH	SO YD
47+63.25	16' RT	1	72	1	1	12
47+63.25	16' LT	1	62	1	1	11
49+76.75	16' RT	1	83	1	1	9
49+76.75	16' LT	1	73	1	1	7
TOTALS		4	290	4	4	39

FILE NAME = D978231-shr-schedule.dgn  
MODEL = Default  
PLOT DRIVER = 100T\_PDF.plt



USER NAME = twalker  
FILE NAME = D978231-shr-schedule.dgn  
PLOT SCALE = 100.0000' / 1in.  
PLOT DATE = 7/9/2014

DESIGNED - MCV  
DRAWN - CMM  
CHECKED - MTM  
DATE -

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES  
SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
877	100B-1	WHITE	54	10
CONTRACT NO. 78231				
ILLINOIS FED. AID PROJECT				