

ACHSIP ACN HPP
90/10 FED/ST 80/20 FED/ST

ACHSIP ACN HPP
90/10 FED/ST 80/20 FED/ST

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0021 URBAN	0005 RURAL
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	301	301	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	19688	18534	1154
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1402	1402	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	297	297	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	767	767	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	119	119	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	10442	9750	692
* 72000100	SIGN PANEL - TYPE 1	SO FT	190	190	
* 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	4	4	
* 72400310	REMOVE SIGN PANEL - TYPE 1	SO FT	50	50	
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1	
* 72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	2	2	
* 72500300	OBJECT MARKER - TYPE 3	EACH	2	2	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0021 URBAN	0005 RURAL
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	514	514	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	301	301	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16471	16471	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1402	1402	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	297	297	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	767	767	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	83	83	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3217	2063	1154
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	36	36	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	231	231	
78300100	PAVEMENT MARKING REMOVAL	SO FT	1224	1224	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	42	42	
* 89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	2	2	

(7) * SPECIALTY ITEMS

FILE NAME :	USER NAME : steffannk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\steffannk\d0158776\074423-shc\soq.dgn	DRAWN -	REVISED -	91			5N	Coles	271	7	
PLOT SCALE = 1/8" = 100'-0"	CHECKED -	REVISED -	CONTRACT NO. 74423							
PLOT DATE = 5/19/2014	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
		SCALE: NA			SHEET 4 OF 6 SHEETS			STA. TO STA.		