

PAVING SCHEDULE																				
STATION	TO	STATION	LENGTH FEET	PAVEMENT WIDTH FEET	SHOULDER WIDTH FEET	AREA SQ YD	BITUMINOUS MATERIALS (PRIME COAT) POUNDS	PAVEMENT REMOVAL SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, 1" SQ YD	PAVED SHOULDER REMOVAL SQ YD	HOT-MIX ASPHALT BASE COURSE, 8 3/4" SQ YD	HOT-MIX ASPHALT BINDER COURSE, N70, 1L-19.0 TON	HOT-MIX ASPHALT BINDER COURSE, N90, 1L-19.0 TON	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N70 TON	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N90 TON	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N90 TON	HOT-MIX ASPHALT SHOULDERS, 8" TON	AGGREGATE SHOULDERS, TYPE B TON	AGGREGATE WEDGE SHOULDER, TYPE B TON	PAVEMENT REMOVAL (SPECIAL) SQ YD
IL 16																				
599+20.17	TO	600+50.27	130.1	36.0	16.0	520.4	117.1	0.0	520.4	88.3	128.4	0.0	0.0	0.0	0.0	58.3	103.6	0.0	0.0	0.0
600+50.27	TO	601+70.00	119.7	36.0	16.0	478.9	107.8	0.0	478.9	64.6	165.9	0.0	0.0	0.0	0.0	53.6	95.3	0.0	0.0	0.0
601+70.00	TO	604+35.00	265.0	Variable	VAR.	1,295.6	291.5	0.0	1,295.6	67.4	599.5	0.0	0.0	0.0	0.0	145.1	171.5	0.0	0.0	0.0
604+35.00	TO	605+77.97	143.0	52.0	VAR.	826.0	185.9	0.0	826.0	36.2	450.3	0.0	0.0	0.0	0.0	92.5	85.4	0.0	0.0	0.0
605+77.97	TO	609+21.13	343.2	Variable	16.0	941.8	211.9	0.0	941.8	88.1	941.8	0.0	0.0	0.0	0.0	105.5	208.7	0.0	0.0	0.0
609+21.13	TO	611+00.00	178.9	36 & Variable	16.0	711.5	160.1	0.0	711.5	25.2	229.2	0.0	0.0	0.0	0.0	79.7	285.0	0.0	0.0	0.0
611+00.00	TO	616+45.89	545.9	Variable to 26	16.0	1,983.4	446.3	0.0	1,983.4	132.0	505.4	0.0	0.0	0.0	0.0	222.1	117.0	0.0	0.0	0.0
E. Harrison Ave. (A)																				
20+00.00	TO	20+50.00	50.0	Variable	8.0	127.2	28.6	0.0	0.0	0.0	0.0	0.0	41.0	0.0	15.4	0.0	0.0	19.7	0.0	0.0
20+50.00	TO	22+30.98	181.0	24.0	8.0	482.6	108.6	0.0	0.0	0.0	0.0	0.0	155.4	0.0	58.3	0.0	0.0	71.5	0.0	0.0
22+30.98	TO	24+33.69	202.7	Variable	8.0	630.7	141.9	0.0	0.0	0.0	0.0	0.0	203.1	0.0	75.4	0.0	0.0	80.0	0.0	0.0
24+33.69	TO	26+28.56	194.9	Variable	8.0	755.7	170.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	89.2	0.0	0.0	120.7	0.0	0.0
26+28.56	TO	27+33.69	105.1	Variable	8.0	845.0	190.1	0.0	0.0	0.0	830.0	0.0	0.0	0.0	72.2	0.0	0.0	0.0	0.0	0.0
27+33.69	TO	27+84.83	51.1	NA	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
27+84.83	TO	28+64.85	80.0	Variable	0.0	543.4	122.3	0.0	0.0	0.0	670.8	0.0	0.0	0.0	58.2	0.0	0.0	0.0	0.0	0.0
28+64.85	TO	30+98.40	233.6	Variable	8.0	1,165.2	262.2	0.0	0.0	0.0	1070.3	0.0	375.2	0.0	135.9	0.0	0.0	144.7	0.0	0.0
30+98.40	TO	32+05.40	107.0	38.0	8.0	451.8	101.7	0.0	0.0	0.0	0.0	0.0	145.5	0.0	53.1	0.0	0.0	42.2	0.0	0.0
32+05.40	TO	32+54.30	48.9	38.0	8.0	206.5	46.5	0.0	0.0	0.0	0.0	0.0	66.5	0.0	24.3	0.0	0.0	19.3	0.0	0.0
32+54.30	TO	34+25.00	170.7	12.0		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	67.4	0.0	0.0
E. Harrison Ave. (B)																				
50+00.00	TO	50+19.00	19.0	NA	8.0	NA	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	7.5	0.0	0.0
50+19.00	TO	50+58.89		Variable		182.7	41.1	0.0	0.0	0.0	0.0	58.8	0.0	20.5	0.0	0.0	0.0	7.9	0.0	0.0
50+58.89	TO	72+25.00	2,166.1	24.0	8.0	5,776.3	1,299.7	0.0	0.0	0.0	0.0	1860.0	0.0	646.9	0.0	0.0	0.0	855.2	0.0	0.0
Connector Rd.																				
0+00.00	TO	0+12.00	12.0	NA	8.0	NA	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	4.7	0.0	0.0
0+12.00	TO	0+52.00	40.0	Variable	8.0	183.0	41.2	0.0	0.0	0.0	0.0	58.9	0.0	20.5	0.0	0.0	0.0	15.8	0.0	0.0
0+52.00	TO	1+94.50	142.5	24.0	8.0	380.0	85.5	0.0	0.0	0.0	0.0	122.4	0.0	42.6	0.0	0.0	0.0	1.0	0.0	0.0
1+94.50	TO	2+44.18	49.7	Variable	8.0	209.8	47.2	0.0	0.0	0.0	0.0	67.6	0.0	23.5	0.0	0.0	0.0	19.6	0.0	0.0
2+44.18	TO	2+54.12	9.9	NA	8.0	NA	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	3.9	0.0	0.0
SHEET TOTALS			5,388			18,697	4,207	0	6,758	502	5,592	2,168	987	754	582	757	1,067	1,481	0	0