

PAVING SCHEDULE (Cont' d)		LENGTH	PAVEMENT WIDTH	SHOULDER WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	PAVED SHOULDER REMOVAL	HOT-MIX ASPHALT BASE COURSE, 8 3/4"	HOT-MIX ASPHALT BINDER COURSE, N70, 1L-19.0	HOT-MIX ASPHALT BINDER COURSE, N90, 1L-19.0	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N70	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N90	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N90	HOT-MIX ASPHALT SHOULDERS, 8"	AGGREGATE SHOULDERS, TYPE B	AGGREGATE WEDGE SHOULDER, TYPE B	PAVEMENT REMOVAL (SPECIAL)	
STATION TO	STATION	FEET	FEET	FEET	SQ YD	POUNDS	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON	SQ YD	TON	TON	SQ YD	
Existing E. Harrison Ave.																				
6+00.00	TO 7+50.65	150.7	22.0	0.0	368.3	0.0	368.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
7+50.65	TO 13+40.12	589.5	20.0	0.0	1,309.9	0.0	1309.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
13+40.12	TO 14+46.51	106.4	Variable	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
14+46.51	TO 14+72.86	26.3	NA	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
14+72.86	TO 15+80.51	107.7	Variable	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
15+80.51	TO 23+75.00	794.5	20.0	0.0	1,765.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
23+75.00	TO 34+71.04	1,096.0	20.0	0.0	2,435.6	0.0	2435.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
34+71.04	TO 41+36.00	665.0	20.0	0.0	1,477.7	332.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	124.1	0.0	0.0	0.0	0.0	37.9	0.0
41+36.00	TO 76+95.00	3,559.0	20.0	0.0	7,908.9	1,779.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	664.3	0.0	0.0	0.0	0.0	202.7	0.0
76+95.00	TO 87+07.00	1,012.0	21.5	0.0	2,417.6	544.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	203.1	0.0	0.0	0.0	0.0	57.6	0.0
87+07.00	TO 87+51.00	44.0	20.0	0.0	97.8	22.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	8.2	0.0	0.0	0.0	0.0	2.5	0.0
Frontage Rd.																				
0+00.00	TO 7+17.02	7+17.02	VARIABLE	0.0	961.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	961.0
SHEET TOTALS		8,868			18,742	2,678	4,114	0	0	0	0	0	0	1,000	0	0	0	0	301	961
PROJECT TOTALS		14,256			37,440	6,885	4,114	6,758	502	5,592	2,168	987	1,754	582	757	1,067	1,481	301	961	

SUB-BASE GRANULAR MATERIAL, TYPE B, 12"

LOCATION			LENGTH (FT)	WIDTH (FT)	AREA (SQ FT)	QUANTITY (SQ YD)	
20+00.00	TO	20+50.00	50.0	25.9	1,295.0	143.9	E. Harrison Ave. (A)
20+50.00	TO	22+50.00	200.0	27	5,400.0	600.0	
68+50.00	TO	72+25.00	375.0	27	10,125.0	1,125.0	E. Harrison Ave. (B)
TOTAL =						1,869.0	