

TREE REMOVAL (6-15 UNITS DIAMETER) SCHEDULE

LOCATION	TOTAL UNITS
IL 16	
608+80.75 RT. 62.8'	11.2
608+80.75 RT. 62.8'	7.0
611+59.91 RT. 49.8'	15.5
611+59.91 RT. 49.8'	15.0
611+72.64 RT. 53.1'	11.0
615+47.68 RT. 57.6'	6.8
615+47.68 RT. 57.6'	13.0
E. HARRISON AVE. (B)	
57+42.51 LT. 33.9'	12.0
57+46.88 LT. 36.1'	14.0
57+50.61 LT. 33.1'	8.0
57+50.96 LT. 31.4'	8.0
57+52.67 LT. 30.3	6.0
57+53.42 LT. 31.2'	6.0
57+62.06 LT. 32.6'	10.0
57+90.49 LT. 11.5'	11.0
57+97.34 LT. 11.4'	9.0
58+02.26 LT. 7.5'	8.0
58+02.94 LT. 6.0'	8.0
58+03.72 LT. 5.0'	6.0
58+07.76 LT. 5.7'	11.0
58+10.56 LT. 3.7'	7.0
58+17.81 LT. 1.9'	9.0
58+17.84 RT. 3.1'	9.0
58+18.26 RT. 3.9'	10.0
58+28.62 RT. 12.6'	6.0
58+34.93 RT. 18.3'	9.0
58+35.52 RT. 16.8'	7.0
58+37.03 RT. 19.7'	11.0
58+37.98 RT. 17.3'	6.0
58+38.12 RT. 17.8'	6.0
58+38.32 RT. 20.0'	8.0
58+42.49 RT. 17.7'	12.0
58+46.19 RT. 24.7'	10.0
58+56.24 RT. 30.2'	14.0
58+56.71 RT. 31.4'	13.0
58+62.98 RT. 32.7'	6.0
58+67.23 RT. 39.0'	9.0
71+05.64 RT. 42.1'	14.0
71+07.09 RT. 43.2'	9.0
71+14.88 RT. 41.2'	15.0
EX. E. HARRISON AVE.	
26+57.47 LT. 73.2'	14.0
26+59.00 LT. 71.7'	11.0
26+59.43 LT. 84.8'	10.5
TOTAL =	422.0

TREE REMOVAL (OVER 15 UNITS DIAMETER) SCHEDULE

LOCATION	TOTAL (UNITS)
E. HARRISON AVE. (A)	
21+74.24 RT. 29.8'	24.0
E. HARRISON AVE. (B)	
57+95.12 RT. 12.9'	18.0
58+31.93 RT. 11.4'	16.0
68+52.81 RT. 35.0'	23.0
EX. E. HARRISON AVE.	
26+57.47 LT. 70.7'	16.0
26+60.91 LT. 87.9'	25.0
TOTAL =	122.0

PATCHING SCHEDULE

LOCATION	CLASS D PATCHES, TYPE II, 15" SQ YD
IL 16	504

EARTHWORK SCHEDULE

Location	Earth Excavation CU. YD.	Earth Excavation Adj. for Shrinkage CU. YD.	Embankment CU. YD.	Earthwork Balance Waste (+)/Shortage (-) CU. YD.
IL 16	CU. YD.	CU. YD.	CU. YD.	CU. YD.
STA. 599+00 TO STA. 616+50 (RT/LT)	4,735.0	3,551.25	1,776.0	+1775.25
E. HARRISON AVE. (A)				
STA. 19+75 TO STA. 34+50 (RT/LT)	6,699.0	5,024.25	936.0	+4088.25
E. HARRISON AVE. (B)				
STA. 50+00 TO STA. 72+50 (RT/LT)	5,722.0	4,291.50	11,425.0	-7133.50
CONNECTOR RD.				
STA. 0+00 TO STA. 2+50 (RT/LT)	73.0	54.75	1,332.0	-1277.25
EXISTING E. HARRISON AVE.				
STA. 8+00 TO STA. 31+50 (RT/LT)	1,228.0	0.0	0.0	0.0
PE 1 (STA. 20+89.55 E. HARRISON (A) LT.)				
STA. 0+00 TO STA. 0+50	10.0	7.50	21.0	-13.50
FE 1 (STA. 21+66.65 (E. HARRISON (A) LT.)				
STA. 0+00 TO STA. 0+50	1.0	0.75	55.0	-54.25
PE 2 (STA. 21+49.95 (E. HARRISON (A) RT.)				
STA. 0+00 TO STA. 0+70	17.0	12.75	55.0	-42.25
PE 3 (STA. 67+89.16 (E. HARRISON (B) LT.)				
STA. 0+00 TO STA. 1+10	3.0	2.25	164.0	-161.75
PE 4 (STA. 69+62.15 E. HARRISON (B) RT.)				
STA. 0+00 TO STA. 0+80	7.0	5.25	40.0	-34.75
FE 2 (STA. 21+50 (EX. E. HARRISON RT.)				
STA. 0+10 TO STA. 0+70	0.0	0.0	41.0	-41.0
FE 3 (STA. 23+50 EX. E. HARRISON RT.)				
STA. 0+00 TO STA. 0+60	10.0	7.50	58.0	-50.50
FE 3 (STA. 616+50 IL 16 RT.)				
STA. 0+10 TO STA. 0+70	10.0	7.50	138.0	-130.5
PROJECT TOTAL	18,515.0	12,965.25	16,041.0	-3075.75

*EARTH EXCAVATION FOR EXISTING E. HARRISON AVE. IS SHOWN ON TOTAL BUT, NOT INCLUDED IN TOTAL FOR ADJUSTED FOR SHRINKAGE OR EARTHWORK BALANCE