

SEEDING SCHEDULE			LENGTH	SEEDING, CLASS 2	NITROGEN FERTILIZER NUTRIENT	PHOPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING
STATION	TO	STATION	FEET	ACRE	POUND	POUND	POUND	TON	ACRE	POUND
IL 16										
599+00.00	TO	606+50.00	750.0	0.5	47.5	47.5	47.5	1.1	0.5	52.8
599+00.00	TO	606+50.00	750.0	0.5	47.6	47.6	47.6	1.1	0.5	52.8
608+50.00	TO	616+45.89	795.9	0.6	50.5	50.5	50.5	1.1	0.6	56.1
608+50.00	TO	616+45.89	795.9	0.6	57.5	57.5	57.5	1.3	0.6	63.9
E. Harrison Ave. (A)										
20+00.00	TO	27+22.53	722.5	0.4	37.5	37.5	37.5	0.8	0.4	41.6
20+00.00	TO	27+22.53	722.5	0.4	37.2	37.2	37.2	0.8	0.4	41.3
27+80.99	TO	34+25.00	644.0	0.3	22.7	22.7	22.7	0.5	0.3	25.2
27+80.99	TO	34+25.00	644.0	0.3	26.1	26.1	26.1	0.6	0.3	29.0
E. Harrison Ave. (B)										
50+50.00	TO	72+25.00	2,175.0	1.3	116.7	116.7	116.7	2.6	1.3	129.6
50+50.00	TO	72+25.00	2,175.0	1.4	124.9	124.9	124.9	2.8	1.4	138.8
Connector Rd.										
0+15.83	TO	2+18.90	203.1	0.1	9.7	9.7	9.7	0.2	0.1	10.8
0+15.83	TO	2+18.90	203.1	0.1	9.5	9.5	9.5	0.2	0.1	10.6
Existing E. Harrison Ave.										
8+00.00	TO	14+00.00	600.0	0.5	43.4	43.4	43.4	0.0	0.5	48.2
15+00.00	TO	16+55.90	155.9	0.2	15.7	15.7	15.7	0.0	0.2	17.4
22+90.78	TO	31+50.00	859.2	0.8	67.7	67.7	67.7	0.0	0.8	75.2
PROJECT TOTALS			12,196	8	714	714	714	13	8	793

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
ci:\pw\work\p\dot\steffenmk\d0158776\074423-shd-sch.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/7/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: NA SHEET 6 OF 13 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
91	5N	Coles	271	28
CONTRACT NO. 74423			ILLINOIS FED. AID PROJECT	